

AD-A101 246

GAI CONSULTANTS INC MONROEVILLE PA

F/G 13/13

NATIONAL DAM INSPECTION PROGRAM. PICKERAL POND DAM (NDI I.D. NU-ETC(U)


JUN 81 8 M MIHALCIN

DACW31-81-C-0015

NL

UNCLASSIFIED

1 of 2
AD-A101 246



AD A101246

DELAWARE RIVER BASIN
BUSH KILL CREEK, PIKE COUNTY

①

PENNSYLVANIA

PICKERAL POND DAM


(NDI I.D. NO. PA-00755

PENNDER I.D. NO. 52-8)

LEVEL II

~~PORTERS LAKE HUNTING AND~~
FISHING ASSOCIATION

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
JUL 13 1981
S E D

PREPARED FOR

"Original contains color
plates: All DTIC reproduct-
ions will be in black and
white"

DEPARTMENT OF THE ARMY

Baltimore District, Corps of Engineers

Baltimore, Maryland 21203

DACW 31-81-C-0015

PREPARED BY

GAI CONSULTANTS, INC.

570 BEATTY ROAD

MONROEVILLE, PENNSYLVANIA 15146

JUNE 1981

DISTRIBUTION STATEMENT

Approved for public release;
Distribution Unlimited

81 7 10 003

DTIC FILE COPY

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the Spillway Design Flood is based on the estimated Probable Maximum Flood (greatest reasonably possible storm runoff) for the region, or fractions thereof. The Spillway Design Flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition, and the downstream damage potential.

Breach analyses are performed, when necessary, to provide data to assess the potential for downstream damage and possible loss of life. The results are based on specific theoretical scenarios peculiar to the analysis of a particular dam and are not applicable to other related studies such as those conducted under the Federal Flood Insurance Program.

Original and color
plates and all reproductions
will be in black and
white.

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Pickeral Pond Dam: NDI I.D. No. PA-00755

Owner: Porters Lake Hunting and Fishing
Association

State Located: Pennsylvania (PennDER I.D. No. 52-8)

County Located: Pike

Stream: Bush Kill Creek

Inspection Date: 12 October 1980

Inspection Team: GAI Consultants, Inc.
570 Beatty Road
Monroeville, Pennsylvania 15146

Based on a visual inspection, operational history, and available engineering data, the dam is considered to be in fair condition.

The size classification of the facility is intermediate and its hazard classification is considered to be high. In accordance with the recommended guidelines, the Spillway Design Flood (SDF) for the facility is the PMF (Probable Maximum Flood). Results of the hydrologic and hydraulic analysis indicate the facility will pass and/or store only about 40 percent of the PMF prior to embankment overtopping. A breach analysis indicates that failure under less than 1/2 PMF conditions could lead to increased downstream damage and potential for loss of life. Thus, based on screening criteria provided in the recommended guidelines, the spillway is considered to be seriously inadequate and the facility unsafe, non-emergency.

It is recommended that the owner immediately:

a. Develop a formal emergency warning system to notify downstream residents should hazardous embankment conditions develop. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

b. Retain the services of a registered professional engineer experienced in the hydrology and hydraulics of dams to further assess the adequacy of the spillway and prepare recommendations for remedial measures deemed necessary to make the facility hydraulically adequate.

c. Restore the operation of the outlet conduit at the upstream control mechanism and repair or replace its upstream and downstream headwalls.


Pickeral Pond Dam: NDI I.D. No. PA-00755


d. Repair concrete deterioration associated with the spillway overflow weir and right sidewall.

e. Clear all excess vegetation from the embankment crest and slopes on a regular routine basis in order to maintain an unobstructed view of the facility.


f. Develop formal manuals of operation and maintenance to ensure the future proper care of the facility.

GAI Consultants, Inc.


Bernard M. Mihaicin, P.E.



Approved by:


JAMES W. PECK
Colonel, Corps of Engineers
Commander and District Engineer

Date 5 June 1981

Date 19 JUNE 1981

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<i>from SD per</i>
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	



View from right abutment.



View from left abutment.

OVERVIEW PHOTOGRAPHS

TABLE OF CONTENTS

	<u>Page</u>
PREFACE.	i
ABSTRACT	ii
OVERVIEW PHOTOGRAPHS	iv
TABLE OF CONTENTS.	v
SECTION 1 - GENERAL INFORMATION.	1
1.0 Authority.	1
1.1 Purpose.	1
1.2 Description of Project	1
1.3 Pertinent Data	2
SECTION 2 - ENGINEERING DATA	5
2.1 Design	5
2.2 Construction Records	6
2.3 Operational Records.	6
2.4 Other Investigations	6
2.5 Evaluation	6
SECTION 3 - VISUAL INSFECTION.	7
3.1 Observations	7
3.2 Evaluation	8
SECTION 4 - OPERATIONAL PROCEDURES	9
4.1 Normal Operating Procedure	9
4.2 Maintenance of Dam	9
4.3 Maintenance of Operating Facilities.	9
4.4 Warning System	9
4.5 Evaluation	9
SECTION 5 - HYDROLOGIC/HYDRAULIC EVALUATION.	10
5.1 Design Data.	10
5.2 Experience Data.	10
5.3 Visual Observations.	10
5.4 Method of Analysis	10
5.5 Summary of Analysis.	10
5.6 Spillway Adequacy.	13
SECTION 6 - EVALUATION OF STRUCTURAL INTEGRITY	14
6.1 Visual Observations.	14
6.2 Design and Construction Techniques	14
6.3 Past Performance	14
6.4 Seismic Stability.	14
SECTION 7 - ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES.	16
7.1 Dam Assessment	16
7.2 Recommendations/Remedial Measures.	16

TABLE OF CONTENTS

APPENDIX A - VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES
APPENDIX B - ENGINEERING DATA CHECKLIST
APPENDIX C - PHOTOGRAPHS
APPENDIX D - HYDROLOGIC AND HYDRAULIC ANALYSES
APPENDIX E - FIGURES
APPENDIX F - GEOLOGY

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM
PICKERAL POND DAM
NDI# PA-00755, PENNDE# 52-8

SECTION 1
GENERAL INFORMATION

1.0 Authority

The Dam Inspection Act, Public Law 92-367, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of inspection of dams throughout the United States.

1.1 Purpose.

The purpose is to determine if the dam constitutes a hazard to human life or property.

1.2 Description of Project.

a. Dam and Appurtenances. Pickeral Pond Dam is 14-foot high earth embankment approximately 337 feet long, including spillway. The facility is constructed with an uncontrolled, rectangular shaped, two-stage, concrete spillway located at the left abutment. The spillway has an ogee-type crest and is 160 feet long. Drawdown capability is provided by a 24-inch diameter, concrete encased, steel pipe located in the embankment to the right of the spillway. Flows through the conduit are controlled at the inlet by means of a 24-inch diameter sluice gate that is manually operated from the upstream embankment face.

b. Location. Pickeral Pond Dam is located on Bush Kill Creek in Porter Township, Pike County, Pennsylvania. The reservoir is situated just off Pennsylvania Route 402, immediately adjacent to Porters Lake and less than three miles south of Pecks Pond. The dam and reservoir are contained within the Pecks Pond, Pennsylvania 7.5 minute U.S.G.S. topographic quadrangle (see Figure 1, Appendix E). The coordinates of the dam are N41° 15.1' and W75° 5.2'.

c. Size Classification. Intermediate (14 feet high, 2800 acre-feet storage capacity at top of dam).

d. Hazard Classification. High (see Section 3.1.e).

e. Ownership. Porters Lake Hunting and Fishing Association
SR Box 518
Dingmans Ferry, Pennsylvania 18328
Attn: Charles W. Miller
President

f. Purpose. Recreation.

g. Historical Data. Information contained in PennDER files indicates that Pickeral Pond predates the earliest available correspondence dated 1919. At that time, Pickeral Pond was reportedly impounded by a six foot high timber crib and stone fill structure. In 1925, the facility was replaced by a seven foot high concrete and stone fill structure. A small power plant was constructed as an appurtenance to the facility in 1928 and remained in operation until 1933. Remnants of the turbine sluiceway are still evident today downstream of the dam.

The present facility was constructed in 1950-51 immediately downstream of the concrete and stone fill structure. The facility was designed by Edward C. Hess of Stroudsburg, Pennsylvania, and was reportedly constructed by Litt Brothers, a local contractor. The facility has been inspected by state officials three times since its completion. Inspection reports dated 1951, 1956, and 1965 indicate the facility has been in generally good to excellent condition with no significant deficiencies cited.

The structure was apparently modified soon after its completion as state highway department officials became aware that the new facility could cause flooding along Pennsylvania Route 402 during minor storms. Normal pool level was subsequently lowered by means of notches cut through the spillway weir shown in Photograph 5.

Pickeral Pond Dam has been owned and operated throughout its entire history by the Porters Lake Hunting and Fishing Association.

1.3 Pertinent Data.

a. Drainage Area (square miles). 23.0.

b. Discharge at Dam Site.

Discharge Capacity of Outlet Conduit - Discharge curves are not available.

Discharge Capacity of Spillway at Maximum Pool = 7,740 cfs (see Appendix D, Sheet 10).

c. Elevations (feet above mean sea level). The following elevations were obtained through field measurements based on the elevation of normal pool at 1311.0 feet as indicated in Figure 1 (see Appendix D, Sheet 2).

Top of Dam	1317.7 (field).
	1318.0 (design).
Maximum Design Pool	Not known.

Maximum Pool of Record	Not known.
Normal Pool	1311.0 (assumed datum).
Spillway Crest	1311.0 (lower stage).
	1311.5 (upper stage).
Upstream Inlet Invert	1306.9 (design).
Downstream Outlet Invert	1306.5 (design).
	1305.6 (field).
Downstream Embankment Toe	1303.7 (field).
Streambed at Dam Centerline	1305 (estimated).
d. <u>Reservoir Length (feet).</u>	
Top of Dam	11000
Normal Pool	4500
e. <u>Storage (acre-feet).</u>	
Top of Dam	2800
Normal Pool	360
f. <u>Reservoir Surface (acres).</u>	
Top of Dam	624
Normal Pool	155
g. <u>Dam.</u>	
Type	Earth.
Length	177 feet (excluding spillway).
Height	14 feet (field measured; embankment crest to downstream embankment toe).
Top Width	10 feet.
Upstream Slope	2-1/2H:1V (design). 2H:1V (field).
Downstream Slope	2H:1V (design). 2H:1V (field).
Zoning	Homogeneous earth fill with a concrete corewall along the embankment centerline (see Figure 3).
Impervious Core and Cutoff	Concrete corewall, 15-inches wide at the top and 36-inches wide at the base, reportedly extends a minimum of two feet into the rock foundation.

	Grout Curtain	None.
h.	<u>Diversion Canal and Regulating Tunnels.</u>	None.
i.	<u>Spillway.</u>	
	Type	Uncontrolled, rectangular shaped, two-stage, concrete spillway with an ogee-type weir located at the left abutment.
	Crest Elevation	1311.0 (lower stage). 1311.5 (upper stage).
	Crest Length	160 feet.
j.	<u>Outlet Conduit.</u>	
	Type	24-inch diameter, concrete encased, steel pipe located in the embankment to the right of the spillway.
	Length	65 feet (estimate).
	Closure and Regulating Facilities	Flows through the outlet conduit are controlled by means of a slide gate located at the inlet.
	Access	The gate control mechanism is accessible from the upstream embankment face when pool levels are at or below normal.

SECTION 2

ENGINEERING DATA

2.1 Design.

a. Design Data Availability and Sources. No formal design reports or calculations are available concerning any aspect of the facility. PennDER files contain several design drawings, the most significant of which has been included in Appendix E of this report (see Figure 3). These files also contain extensive correspondence dating back to 1919 along with dated photographs and three state inspection reports pertaining to the present facility. A state issued construction permit application report, dated 1950, contains brief discussions of the various design aspects of the present facility.

b. Design Features.

1. Embankment. Design features of the embankment are presented in Figure 3. As indicated, the embankment essentially comprises the right half of the structure and is 177 feet long and approximately 14 feet high. The embankment consists of homogeneous earthfill with a concrete corewall constructed along its centerline through its entire length. The corewall is 15 inches thick at the top with 1H:12V battered sides. It reportedly extends from 3.5 feet beneath the embankment crest into the foundation below the ground surface a minimum depth of two feet into solid rock. The design slopes were set at 2-1/2H:1V and 2H:1V for the upstream and downstream embankment slopes, respectively. However, both the upstream and downstream embankment slopes were field measured at 2H:1V. The upstream embankment face is protected with a 12-inch thick riprap layer. The design intended that embankment material be placed in six inch layers and thoroughly compacted with a 10-ton roller.

2. Appurtenant Structures.

a) Spillway. Design features of the spillway are presented in Figure 3. As indicated, the spillway comprises the left half of Pickeral Pond Dam. The spillway is a concrete-gravity type, ogee section, four feet high and six feet wide at the base, constructed on solid rock (see Photograph 5). A concrete sidewall abuts the right end of the spillway against the embankment while the left end of the spillway is tied into bedrock at the left abutment hillside.

b) Outlet Conduit. Design features of the outlet conduit are presented in Figure 3. As indicated, the outlet conduit is a 24-inch diameter, concrete encased, steel pipe located approximately 55 feet from the right abutment. The conduit was designed such that flows would be controlled at the inlet by means of a 24-inch diameter sluice gate.

c. Specific Design Data and Criteria. No specific design data or information relative to design procedures are available other than the general information contained in PennDER files.

2.2 Construction Records.

No formal construction records are available for this facility. PennDER files do contain various memoranda and correspondence that pertain to construction related activities. In addition, three of the available dated photographs were taken during construction and immediately upon completion of the project.

2.3 Operational Records.

No records of the day-to-day operation of the facility are available.

2.4 Other Investigations.

Other than three state inspections performed in 1951, 1956, and 1965, no formal investigations have been conducted on this facility subsequent to its construction.

2.5 Evaluation.

The available data are considered sufficient to make a reasonable Phase I evaluation of the facility.

SECTION 3

VISUAL INSPECTION

3.1 Observations.

a. General. The general appearance of the facility suggests the dam and its appurtenances are in fair condition.

b. Embankment. Observations made during the visual inspection indicate the embankment is in good condition. Heavy overgrowth covers the embankment crest and downstream face, indicative of a general lack of adequate maintenance (see Photographs 2, 3 and 4). Briars and low shrubs, along with at least six large trees (6 to 18 inches in diameter), characterize the vegetation. No evidence of sloughing, erosion, seepage through the downstream embankment face or excessive settlement was observed. Local ponding occurs in a low area located immediately downstream of the embankment. The primary source of the ponded water is the outlet conduit which, although supposedly sealed, leaks profusely at its discharge end (see Photograph 8). Observations suggest some seepage may emanate from along the downstream embankment toe and beyond; however, it does not appear to be significant.

c. Appurtenant Structures.

1. Spillway. The visual inspection revealed the spillway is in fair condition. General concrete deterioration characterizes the entire structure (see Photographs 5 and 6). The right sidewall, in particular, displays cracking, extensive spalling and efflorescence.

2. Outlet Conduit. The outlet conduit was not operated in the presence of the inspection team and is considered to be in poor condition. The gate control mechanism and concrete headwall at the inlet are dilapidated (see Photograph 7). The concrete headwall at the discharge end exhibits excessive concrete deterioration. Based strictly on its appearance, the control mechanism is likely inoperable. The non-functional gate has resulted in a fully flooded conduit that had to be closed off at the discharge end. A flat steel plate supported by steel angles has been placed across the discharge end of the conduit and acts as a seal. The top angle has broken free, resulting in leakage estimated at 30 to 40 gpm (see Photograph 8).

d. Reservoir Area. The general area surrounding the Pickeral Pond watershed consists of moderate, heavily forested slopes. The exception is a large swamp, known as Wolf Swamp, located to the immediate northeast of the pond. No evidence of slope distress was observed.

The 23-square mile Pickeral Pond watershed contains five substantial water impounding facilities (see Figure 2). These

include: 1) Blue Heron Lake Dam (PennDER I.D. No. 52-9); 2) Hemlock Dam (PennDER I.D. No. 52-71); 3) Lower Hemlock Dam (PennDER I.D. No. 52-117); 4) Pecks Pond Dam (PennDER I.D. No. 52-15); and Porters Lake Dam (PennDER I.D. No. 52-33). Statistics pertaining to each of these facilities are included in Appendix D (see Sheets 14 through 22).

e. Downstream Channel. Discharges from Pickeral Pond Dam are channeled into a heavily forested valley with moderate to steep confining slopes. The valley is strewn with both permanent and seasonal dwellings. Approximately one to three miles downstream of the embankment, several dwellings are located sufficiently near the stream as to possibly be affected by the floodwaters resulting from an embankment breach. It is estimated that as many as 15 to 20 persons could inhabit these structures at any given time, particularly on weekends and during the peak season. Consequently, the hazard classification is considered to be high.

3.2 Evaluation.

Based on visual observations, the condition of the facility is considered to be fair. Remedial measures should be implemented to: 1) repair the inlet and outlet portions of the outlet conduit; 2) remove excess vegetation from the embankment crest and slopes; and 3) repair the concrete deterioration associated with the spillway.

SECTION 4

OPERATIONAL PROCEDURES

4.1 Normal Operating Procedures.

Pickeral Pond Dam is essentially a self-regulating facility. That is, excess inflows are automatically discharged through the uncontrolled spillway and directed downstream. The outlet conduit has been partially sealed at its discharge end and is presently non-functional. No formal operations manual is available.

4.2 Maintenance of Dam.

The owner reportedly maintains the dam on an unscheduled, as-needed basis. Conditions observed by the inspection team indicate, however, that maintenance is minimal. No formal maintenance program has been established and no formal manuals are available.

4.3 Maintenance of Operating Facilities.

See Section 4.2 above.

4.4 Warning System.

No formal warning system is presently in effect.

4.5 Evaluation.

The general appearance of the facility suggests a lack of adequate maintenance. No formal maintenance or operations manuals are available, but, are recommended to ensure the future proper care and operation of the facility. In addition, formal warning system procedures should be incorporated into these manuals to provide for the protection of downstream residents should hazardous embankment conditions develop.

SECTION 5

HYDROLOGIC/HYDRAULIC EVALUATION

5.1 Design Data.

No formal design reports are available for this facility. According to information contained in PennDER files, the spillway at Pickeral Pond Dam was sized for a design discharge capacity of about 11,000 cfs. This was based on an uncontrolled, rectangular shaped, two-stage, concrete spillway with an ogee-type weir 171 feet long (coefficient of discharge $C = 3.7$). The capacity of the spillway, as determined by the analysis contained in this report and based on as-built and present day conditions, is approximately 7,700 cfs (see Appendix D, Sheets 6 through 10). The difference is due, in part, to the smaller as-built crest length and, in part, to the head losses attributable to the configuration of the approach channel and the odd angle at which the spillway is situated relative to the approach channel (see Figure 3, Appendix E). These head losses were apparently neglected in the design.

5.2 Experience Data.

Daily records of reservoir levels and/or spillway discharges are not available. The general appearance of the facility suggests adequate past performance.

5.3 Visual Observations.

On the date of inspection, no conditions were observed that would indicate the facility could not perform satisfactorily within the limits of its as-built capacity.

5.4 Method of Analysis.

The facility has been analyzed in accordance with the procedures and guidelines established by the U.S. Army, Corps of Engineers, Baltimore District, for Phase I hydrologic and hydraulic evaluations. The analysis has been performed utilizing a modified version of the HEC-1 program developed by the U.S. Army, Corps of Engineers, Hydrologic Engineering Center, Davis, California. Analytical capabilities of the program are briefly outlined in the preface contained in Appendix D.

5.5 Summary of Analysis.

a. Spillway Design Flood (SDF). In accordance with procedures and guidelines contained in the National Guidelines for Safety Inspection of Dams for Phase I Investigations, the Spillway

Design Flood (SDF) for Pickeral Pond Dam is the PMF (Probable Maximum Flood). This classification is based on the relative size of the dam (intermediate) and the potential hazard of dam failure to downstream developments (high).

b. Results of Analysis. Pickeral Pond Dam was evaluated under near normal operating conditions. That is, the reservoir was initially at the lower stage spillway crest elevation of 1311.0 feet, with the spillway weir discharging freely. The low flow notches cut in the spillway weir were not considered in this analysis (see Appendix D, Sheet 2, Note 1). The outlet conduit was assumed to be non-functional for the purpose of analysis, since the flow capacity of the conduit is not such that it would significantly increase the total discharge capabilities of the facility. The spillway consists of an uncontrolled, rectangular shaped, concrete channel, with discharges regulated by a two-stage, concrete, ogee-type weir.

Five upstream dams were included in the analysis to determine their effects on Pickeral Pond Dam. Pecks Pond Dam, Porters Lake Dam, and Blue Heron Lake Dam each discharge directly into Pickeral Pond, while Hemlock Lake Dam and Lower Hemlock Dam are located in series upstream of Blue Heron Lake Dam (see Figure 2). Each of these dams was evaluated under normal operating conditions. That is, the reservoirs were initially at normal pool, the spillways were assumed to be discharging freely, and, the outlet conduits were assumed to be closed. All pertinent engineering calculations relative to the evaluation of Pickeral Pond Dam, including those pertaining to the upstream facilities, are included in Appendix D.

Overtopping analysis (using the modified HEC-1 computer program) indicated that the discharge/storage capacity of Pickeral Pond Dam can accommodate only about 40 percent of the PMF prior to embankment overtopping. It was also found that Hemlock Dam, Lower Hemlock Dam, Blue Heron Lake Dam, Pecks Pond Dam, and Porters Lake Dam can accommodate about 60 percent, 67 percent, 4 percent, 4 percent, and 2 percent of the PMF, respectively, prior to embankment overtopping. Under PMF (SDF) conditions, the embankment at Pickeral Pond Dam was overtopped for more than 9.0 hours, by depths of up to 5.1 feet. Under 1/2-PMF conditions, the embankment was overtopped for nearly 7.0 hours, by depths of up to 1.1 feet (Appendix D, Summary Input/ Output Sheets, Sheets Q and R). Since the SDF for Pickeral Pond Dam is the PMF, it can be concluded that the dam has a high potential for overtopping, and thus, for breaching under floods of less than SDF magnitude.

Since Pickeral Pond Dam cannot safely pass a flood of at least 1/2 PMF magnitude, the possibility of embankment failure under floods of 1/2 PMF intensity or less was investigated (in accordance with Corps directive ETL-1110-2-234). Although the spillways at Blue Heron Lake Dam, Pecks Pond Dam, and Porters Lake Dam are not capable of safely passing the 1/2 PMF, the possibility of failure at these facilities was not considered.

Several possible alternative failure schemes were examined for Pickeral Pond Dam, since it is difficult, if not impossible, to determine exactly how or if a specific dam will fail. The major concern of the breaching analysis is with the impact of the various breach discharges on increasing downstream water surface elevations above those to be expected if breaching did not occur.

The modified HEC-1 computer program was used for the breaching analysis, with the assumption that the breaching of an earth dam would begin once the low area in the embankment crest was overtopped. Also, in routing the outflows downstream, the channel bed was assumed to be initially dry.

Five possible modes of failure were investigated. Two sets of breach geometry were evaluated for each of two failure times. The two breach sections chosen were considered to be the minimum and maximum probable failure sections. The two failure times (total time for each breach section to reach its final dimensions) under which the minimum and maximum sections were investigated were assumed to be a rapid time (0.5-hour) and a prolonged time (4.0 hours), so that a range of this most sensitive variable might be examined. In addition, an average possible set of breach conditions was analyzed, with a failure time of 1.0-hour (Appendix D, Sheet 24).

The peak breach outflows (resulting from 0.42 PMF conditions) at Pickeral Pond Dam ranged from 8,580 cfs for the minimum section-maximum fail time scheme to about 26,220 cfs for the maximum section-minimum fail time scheme. The peak outflow from the average breach scheme was about 15,300 cfs, compared to the non-breach 0.42 PMF peak outflow of approximately 8,250 cfs (Appendix D, Sheet 26).

Three potential damage centers were investigated in this analysis. At Section 1, about 1.1 miles downstream from Pickeral Pond Dam (see Figure 1), the outflows from the various breach models resulted in water levels ranging from 4.8 feet to 9.5 feet above the damage levels of the nearby dwellings, and 0.1-foot to 4.8 feet above the non-breach levels.

The maximum non-breach water level at Section 2, about 750 feet further downstream (see Figure 1), was approximately 2.0 feet above the damage level of the structures. However, the increases above the non-breach levels resulting from the various failure schemes ranged from 0.1-foot to 4.6 feet, and thus, were as much as 6.6 feet above the damage levels.

At Section 3, located about two miles downstream from the dam (Figure 1), the peak water surface elevations resulting from the breaches ranged up to 7.9 feet above the damage levels of the nearby structures, and up to 3.6 feet above the non-breach peak elevations (Appendix D, Sheet 27).

The consequences of dam failure can better be envisioned if not only the increase in the height of the floodwave is considered, but also the great increase in momentum of the larger and probably swifter moving volume of water. In addition, the possibility of a near instantaneous failure due to the collapse of the concrete corewall was not considered in this analysis, although such a failure is possible and would most likely result in higher downstream water surface elevations. Finally, it is noted that although the non-breach outflows resulted in the inundation of the dwellings nearest the stream at all three hazard centers, the increases in water levels due to the breaches were significant, and would most likely also cause flooding at other structures along these reaches (structures at higher elevations which were noted but not measured in the field inspection).

From this analysis, it is concluded that the failure of Pickeral Pond Dam is quite possible, and would most likely lead to increased property damage and possibly loss of life in the downstream regions.

5.6 Spillway Adequacy.

As presented previously, Pickeral Pond Dam can accommodate only about 40 percent of the PMF (SDF) prior to embankment overtopping. It has been shown that should an event of magnitude greater than this occur, the dam would be overtopped and could possibly fail, endangering downstream residences and increasing the potential for loss of life in the downstream regions. Therefore, the spillway is considered to be seriously inadequate.

SECTION 6

EVALUATION OF STRUCTURAL INTEGRITY

6.1 Visual Observations.

a. Embankment. Based on visual observations, the structural condition of the embankment is considered to be good. The deficiencies encountered can be attributed, for the most part, to a lack of adequate maintenance. The overgrowth observed along the downstream embankment face is considered to be a significant deficiency requiring immediate remedial attention. The root systems of large trees may offer a course for possible piping through the embankment. Furthermore, the existence of trees on the slope which may uproot and topple is a potential threat to the overall stability of the slope. Excess vegetation also obscures clear view of the downstream toe which may become critical in the event of an embankment emergency.

b. Appurtenant Structures.

1. Spillway. The spillway is considered to be in fair condition. The concrete deterioration observed across the overflow weir and right sidewall should be repaired immediately and not allowed to advance to a stage where the stability of the structure would be threatened.

2. Outlet Conduit. The outlet conduit is presently inoperable and considered to be in poor condition. Restoration of the upstream control mechanism and concrete headwalls (upstream and downstream) should be undertaken immediately.

6.2 Design and Construction Techniques.

Little information is available that pertains to the methods of design and/or construction of the facility. Data contained in PennDER files indicates that the entire structure is founded on rock and that the embankment corewall and spillway are keyed several feet into the rock foundation.

6.3 Past Performance.

There are no records documenting any events during which the facility has not adequately functioned.

6.4 Seismic Stability.

The dam is located in Seismic Zone No. 1 and may be subject to minor earthquake induced dynamic forces. As the facility appears to be well constructed and sufficiently stable, it is believed that

it can withstand the expected minor dynamic forces; however, no calculations and/or investigations were performed to confirm this belief.

SECTION 7

ASSESSMENT AND RECOMMENDATIONS FOR REMEDIAL MEASURES

7.1 Dam Assessment.

a. Safety. The results of this investigation indicate the facility is in fair condition.

The size classification of the facility is intermediate and its hazard classification is considered to be high. In accordance with the recommended guidelines, the Spillway Design Flood (SDF) for the facility is the PMF (Probable Maximum Flood). Results of the hydrologic and hydraulic analysis indicate the facility will pass and/or store only about 40 percent of the PMF prior to embankment overtopping. A breach analysis indicates that failure under less than 1/2 PMF conditions could lead to increased downstream damage and potential for loss of life. Thus, based on screening criteria provided in the recommended guidelines, the spillway is considered to be seriously inadequate and the facility unsafe, non-emergency.

b. Adequacy of Information. The available data are considered sufficient to make a reasonable Phase I assessment of the facility.

c. Urgency. The recommendations listed below should be implemented immediately.

d. Necessity for Additional Investigations. An additional hydrologic/hydraulic investigation is currently deemed necessary to more accurately assess the adequacy of the spillway.

7.2 Recommendations/Remedial Measures.

It is recommended that the owner immediately:

a. Develop a formal emergency warning system to notify downstream residents should hazardous embankment conditions develop. Included in the plan should be provisions for around-the-clock surveillance of the facility during periods of unusually heavy precipitation.

b. Retain the services of a registered professional engineer experienced in the hydrology and hydraulics of dams to further assess the adequacy of the spillway and prepare recommendations for remedial measures deemed necessary to make the facility hydraulically adequate.

c. Restore the operation of the outlet conduit at the upstream control mechanism and repair or replace its upstream and downstream headwalls.

d. Repair concrete deterioration associated with the spillway overflow weir and right sidewall.

e. Clear all excess vegetation from the embankment crest and slopes on a regular routine basis in order to maintain an unobstructed view of the facility.

f. Develop formal manuals of operation and maintenance to ensure the future proper care of the facility.

APPENDIX A
VISUAL INSPECTION CHECKLIST AND FIELD SKETCHES

**CHECK LIST
VISUAL INSPECTION
PHASE 1**

NAME OF DAM Pickeral Pond Dam STATE Pennsylvania COUNTY Pike

NDI # PA — 00755 PENNIDER # 52-8

TYPE OF DAM Earth and Rockfill SIZE Intermediate HAZARD CATEGORY High

DATE(S) INSPECTION 12 October 1980 WEATHER Overcast TEMPERATURE 55° @ Noon

POOL ELEVATION AT TIME OF INSPECTION 1309.2 feet M.S.L.

TAILWATER AT TIME OF INSPECTION N/A M.S.L.

INSPECTION PERSONNEL	OWNER REPRESENTATIVES	OTHERS
<u>B.M. Mihalcin</u>	<u>None</u>	
<u>D.J. Spaeder</u>		
<u>D.L. Bonk</u>		

RECORDED BY B.M. Mihalcin

EMBANKMENT

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA. 00755
SURFACE CRACKS	None observed. Entire dam is covered with rock.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	None observed.	
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Horizontal - Good. Vertical - See "Profile of Dam Crest from Field Survey," Appendix A.	
RIPRAP FAILURES	None observed. Riprap is hard, durable sandstone. Individual pieces are somewhat elongated and flat, but well graded and interlocking.	
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Good condition.	

EMBANKMENT

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDIN PA - 00755
DAMP AREAS IRREGULAR VEGETA- TION (LUSH OR DEAD PLANTS)	Local ponding occurs in a low area located immediately beyond the downstream embankment toe. The primary source of the ponded water is the outlet conduit which, although supposedly sealed, leaks profusely at its discharge end. Some of the ponded water may be the result of minor seepage at or beyond the downstream embankment toe.	
ANY NOTICEABLE SEEPAGE	None through downstream embankment. Observations suggest some seepage may emanate from along the downstream embankment toe and beyond; however, it does not appear to be significant.	
STAFF GAGE AND RECORDER	None.	
DRAINS	None observed.	
VEGETATION	At least six (6) large trees (6 to 18 inches diameter) are rooted within the downstream embankment face and should be removed. Briars and low shrubs inhibit observation of the surface of the embankment structure.	
MISCELLANEOUS	Bedrock is exposed throughout the area. Very little soil cover. Spillway and abutments are founded in rock. Dam appears to be an appurtenance to a natural lake.	

OUTLET WORKS

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA · 00755
INTAKE STRUCTURE	Submerged, not observed.	
OUTLET CONDUIT (CRACKING AND SPALLING OF CON- CRETE SURFACES)	Not observed.	
OUTLET STRUCTURE	Poor condition. Concrete headwall exhibits excessive concrete spalling, cracking and general deterioration. A flat steel plate supported by steel angles has been placed across the discharge end of the conduit in order to seal it. Top angle has broken free, resulting in a large leak (30 to 40 gpm) between the plate and conduit headwall.	
OUTLET CHANNEL	Bedrock lined channel. Some ponding occurs immediately beyond the downstream embankment toe in a local low area.	
GATE(S) AND OPERA- TIONAL EQUIPMENT	Dilapidated and inoperable gate control mechanism. Appears to be a steel framed slide gate set in a concrete channel. Frame is broken and concrete is cracked and dislodged.	

EMERGENCY SPILLWAY

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00755
TYPE AND CONDITION	Uncontrolled, rectangular shaped, concrete channel with an ogee-type weir located at the left abutment. Concrete weir and sidewalls in fair condition with severe spalling and general deterioration evident. Channel bottom is bedrock.	
APPROACH CHANNEL	Bedrock lined channel. Partially obstructed by brush and small trees, particularly near the left abutment.	
SPILLWAY CHANNEL AND SIDEWALLS	Left concrete sidewall is small and exists only to tie the concrete weir into the left abutment. Most of the left side of the spillway channel is cut in rock. Right concrete sidewall, abutting the embankment, is in fair condition with local spalling and cracking evident.	
STILLING BASIN PLUNGE POOL	None. Spillway weir discharges into a bedrock lined channel.	
DISCHARGE CHANNEL	Unobstructed, bedrock lined channel.	
BRIDGE AND PIERS EMERGENCY GATES	None.	

SERVICE SPILLWAY


ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00755
TYPE AND CONDITION	N/A.	
APPROACH CHANNEL	N/A.	
OUTLET STRUCTURE	N/A.	
DISCHARGE CHANNEL	N/A.	

INSTRUMENTATION

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA · 00755
MONUMENTATION SURVEYS	None.	
OBSERVATION WELLS	None.	
WEIRS	None.	
PIEZOMETERS	None.	
OTHERS	None.	

RESERVOIR AREA AND DOWNSTREAM CHANNEL

ITEM	OBSERVATIONS/REMARKS/RECOMMENDATIONS	NDI# PA - 00755
SLOPES: RESERVOIR	Moderate slopes that are heavily forested. Bedrock exposed all around general area surrounding the reservoir. Very little soil cover.	
SEDIMENTATION	Lake apparently floods an old swamp and is very shallow. Many tree stumps project above the water line. No evidence of actual sedimentation was observed.	
DOWNSTREAM CHANNEL (OBSTRUCTIONS, DEBRIS, ETC.)	Rock falls located immediately downstream of embankment.	
SLOPES: CHANNEL VALLEY	Gently sloped channel set in a heavily forested valley with moderate to steep confining slopes.	
APPROXIMATE NUMBER OF HOMES AND POPULATION	Valley downstream of embankment is strewn with permanent and seasonal dwellings. It is estimated that as many as 15 to 20 persons could inhabit several dwellings situated near the stream about one to three miles downstream of the embankment.	



PICKERAL POND DAM
GENERAL PLAN-FIELD INSPECTION NOTES

PICKERAL POND DAM

PROFILE OF DAM CREST
FROM FIELD SURVEY

NOT A PA - 007515

RIGHT
ABUTMENT

TOP OF RIGHT SPILLWAY
SIDEWALL REL. B.T.G.

LOW AREA
REL. B.T.G.

LEFT
ABUTMENT

"UPPER STAGE"
SPILLWAY CREST
REL. B.T.G.

"LOWER STAGE"
SPILLWAY
CREST
REL. B.T.G.

LOW FLOW
NOTCHES

SCALE

VERTICAL: 1 IN = 9 FT
HORIZONTAL: 1 IN = 50 FT

SUBJECT PICKERAL POND DAM
BY 2025 DATE 5-9-21 SHEET NO. OF —
CHECKED BY 3-16 DATE 5-11-21 PROJECT NO. 60-238-755

APPENDIX B
ENGINEERING DATA CHECKLIST

**CHECK LIST
ENGINEERING DATA
PHASE I**

NAME OF DAM Pickeral Pond Dam

ITEM	REMARKS	NDI# PA - 00755
PERSONS INTERVIEWED AND TITLE	Porters Lake Hunting and Fishing Association Charles W. Miller - President Walter Whittaker - caretaker (full-time resident)	
REGIONAL VICINITY MAP	See Figure 1, Appendix E.	
CONSTRUCTION HISTORY	Constructed in 1950-51. Designed by Edward C. Hess of Stroudsburg, PA. Notches cut in spillway weir shortly after completion to lower pool level and prevent frequent flooding of Pennsylvania Route 402.	
AVAILABLE DRAWINGS	None from owner. Design drawing (several revisions) contained in PennDER files (see Figure 3, Appendix E).	
TYPICAL DAM SECTIONS	See Figure 3, Appendix E.	
OUTLETS: PLAN DETAILS DISCHARGE RATINGS	See Figure 3, Appendix E.	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA. 00755
SPILLWAY: PLAN SECTION DETAILS	See Figure 3, Appendix E.	
OPERATING EQUIP. MENT PLANS AND DETAILS	See Figure 3, Appendix E.	
DESIGN REPORTS	None available.	
GEOLOGY REPORTS	None available.	
DESIGN COMPUTATIONS: HYDROLOGY AND HYDRAULICS STABILITY ANALYSES SEEPAGE ANALYSES	None available.	
MATERIAL INVESTIGATIONS: BORING RECORDS LABORATORY TESTING FIELD TESTING	None available.	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA - 00755
BORROW SOURCES	Not known.	
POST CONSTRUCTION DAM SURVEYS	None.	
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None.	
HIGH POOL RECORDS	No formal records are available.	
MONITORING SYSTEMS	None.	
MODIFICATIONS	Cut notches in spillway shortly after completion of construction (1951).	

**CHECK LIST
ENGINEERING DATA
PHASE I
(CONTINUED)**

ITEM	REMARKS	NDI# PA · 00755
PRIOR ACCIDENTS OR FAILURES	None.	
MAINTENANCE: RECORDS MANUAL	No records or manual are available.	
OPERATION: RECORDS MANUAL	No records or manual are available.	
OPERATIONAL PROCEDURES	Self-regulating.	
WARNING SYSTEM AND/OR COMMUNICATION FACILITIES	None.	
MISCELLANEOUS	Two construction photographs showing cutoff trenches founded in bedrock from Pennder files. Also one photograph of completed structure (1951).	

GAI CONSULTANTS, INC.

CHECK LIST
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

NDIID # PA-00755
PENNDER ID # 52-8

SIZE OF DRAINAGE AREA: 4.9 square miles (local); 23.0 square miles (total).

ELEVATION TOP NORMAL POOL: 1311.0 STORAGE CAPACITY: 360 acre-feet

ELEVATION TOP FLOOD CONTROL POOL: - STORAGE CAPACITY: -

ELEVATION MAXIMUM DESIGN POOL: - STORAGE CAPACITY: -

ELEVATION TOP DAM: 1317.7 STORAGE CAPACITY: 2,800 acre-feet
(field)

SPILLWAY DATA

CREST ELEVATION: 1311.0 feet (lower stage); 1311.5 feet (upper stage).

TYPE: Uncontrolled, rectangular, concrete channel with ogee-type weir.

CREST LENGTH: 160 feet.

CHANNEL LENGTH: N/A.

SPILOVER LOCATION: Left abutment.

NUMBER AND TYPE OF GATES: None.

OUTLET WORKS

TYPE: 24-inch diameter, concrete encased steel pipe.

LOCATION: Right of spillway.

ENTRANCE INVERTS: 1306.9 (design).

EXIT INVERTS: 1306.5 (design); 1305.6 (field).

EMERGENCY DRAWDOWN FACILITIES: Slide gate at inlet.

HYDROMETEOROLOGICAL GAGES


TYPE: None.

LOCATION: -

RECORDS: -

MAXIMUM NON-DAMAGING DISCHARGE: Not known.

APPENDIX C
PHOTOGRAPHS



PICKERAL POND DAM
PHOTOGRAPH KEY MAP

PHOTOGRAPH 1 View of Pickeral Pond as seen from the upstream embankment face.

PHOTOGRAPH 2 View of the rock covered upstream embankment face as seen from the right abutment.

PHOTOGRAPH 3 View of the overgrown downstream embankment face as seen from a position along the right abutment about 50 feet downstream of the embankment.

PHOTOGRAPH 4 View of the downstream embankment face as seen from a position about 40 feet downstream of the embankment between the spillway and outlet conduit.



2



4



1



3

PHOTOGRAPH 5 View of the spillway weir looking toward the left abutment.

PHOTOGRAPH 6 View of the deteriorated right spillway sidewall.

PHOTOGRAPH 7 View of the dilapidated outlet conduit control mechanism and upstream headwall.

PHOTOGRAPH 8 View of the partially sealed outlet conduit discharge and deteriorated concrete headwall.



6



8



5



7

APPENDIX D
HYDROLOGIC AND HYDRAULIC ANALYSES

PREFACE

The modified HEC-1 program is capable of performing two basic types of hydrologic analyses: 1) the evaluation of the overtopping potential of the dam; and 2) the estimation of the downstream hydrologic-hydraulic consequences resulting from assumed structural failures of the dam. Briefly, the computational procedures typically used in the dam overtopping analysis are as follows:

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir to determine if the event(s) analyzed would overtop the dam.
- c. Routing of the outflow hydrograph(s) from the reservoir to desired downstream locations. The results provide the peak discharge(s), time(s) of occurrence the peak discharge(s), and the maximum stage(s) of each routed hydrograph at the downstream end of each reach.

The evaluation of the hydrologic-hydraulic consequences resulting from an assumed structural failure (breach) of the dam is typically performed as shown below.

- a. Development of an inflow hydrograph(s) to the reservoir.
- b. Routing of the inflow hydrograph(s) through the reservoir.
- c. Development of a failure hydrograph(s) based on specified breach criteria and normal reservoir outflow.
- d. Routing of the failure hydrograph(s) to desired downstream locations. The results provide estimates of the peak discharge(s), time(s) to peak and maximum water surface elevation(s) of failure hydrograph(s) for each location.

HYDROLOGY AND HYDRAULIC ANALYSIS DATA BASE

NAME OF DAM: PICKERAL POND DAM

PROBABLE MAXIMUM PRECIPITATION (PMP) = 21.5 INCHES/24 HOURS ⁽¹⁾

STATION	1	2	3
STATION DESCRIPTION	HEMLOCK LAKE DAM	LOWER HEMLOCK DAM	BLUE HERON LAKE DAM
DRAINAGE AREA (SQUARE MILES)	1.1	0.1	5.0
CUMULATIVE DRAINAGE AREA (SQUARE MILES)	-	1.2	6.2
ADJUSTMENT OF PMF FOR DRAINAGE AREA LOCATION (%) ⁽¹⁾	ZONE 1	ZONE 1	ZONE 1
6 HOURS	101	101	101
12 HOURS	114	114	114
24 HOURS	124	124	124
48 HOURS	133	133	133
72 HOURS	-	-	-
SNYDER HYDROGRAPH PARAMETERS			
ZONE (2)	1	1	1
C _p (3)	0.45	0.45	0.45
C _t (3)	1.23	1.23	1.23
L (MILES) (4)	-	-	4.5
L _{ca} (MILES) (4)	-	-	2.4
L' (MILES) (4)	0.66	0.31	-
t _p (MILES) (5)	0.96	0.61	2.51
SPILLWAY DATA			
CREST LENGTH (FEET)	47	43.5	24/38 (6)
FREEBOARD (FEET)	3.0	3.3	1.5/1.1 (6)

(1) HYDROMETEOROLOGICAL REPORT 33, U.S. ARMY CORPS OF ENGINEERS, 1956.

(2) HYDROLOGIC ZONE DEFINED BY CORPS OF ENGINEERS, BALTIMORE DISTRICT, FOR DETERMINATION OF SNYDER COEFFICIENTS (C_p AND C_t).

(3) SNYDER COEFFICIENTS

(4) L = LENGTH OF LONGEST WATERCOURSE FROM DAM TO BASIN DIVIDE

L_{ca} = LENGTH OF LONGEST WATERCOURSE FROM DAM TO POINT OPPOSITE BASIN CENTROID.

L' = LENGTH OF LONGEST WATERCOURSE FROM RESERVOIR INLET TO DRAINAGE DIVIDE.

(5) $t_p = C_t (L \cdot L_{ca})^{0.3}$ or $t_p = C_t (L')^{0.6}$

(6) SERVICE/EMERGENCY.

HYDROLOGY AND HYDRAULIC ANALYSIS DATA BASE

NAME OF DAM: PICKERAL POND DAM

PROBABLE MAXIMUM PRECIPITATION (PMP) = 21.5 INCHES/24 HOURS (1)

STATION	4	5	6
STATION DESCRIPTION	PORTERS LAKE DAM	PECKS POND DAM	PICKERAL POND DAM
DRAINAGE AREA (SQUARE MILES)	2.7	9.2	4.9
CUMULATIVE DRAINAGE AREA (SQUARE MILES)	-	-	23.0
ADJUSTMENT OF PMF FOR DRAINAGE AREA LOCATION (%) (1)	ZONE 1	ZONE 1	ZONE 1
6 HOURS	101	101	101
12 HOURS	114	114	114
24 HOURS	124	124	124
48 HOURS	133	133	133
72 HOURS	-	-	-
SNYDER HYDROGRAPH PARAMETERS			
ZONE (2)	1	1	1
C_p (3)	0.45	0.45	0.45
C_t (3)	1.23	1.23	1.23
L (MILES) (4)	4.6	-	3.2
L_{ca} (MILES) (4)	1.8	-	1.8
L' (MILES) (4)	-	2.6	-
t_p (MILES) (5)	2.32	2.18	2.08
SPILLWAY DATA			
CREST LENGTH (FEET)	6.4	30	83/77 (6)
FREEBOARD (FEET)	1.5	2.3	6.7/6.2 (6)

(1) HYDROMETEOROLOGICAL REPORT 33, U.S. CORPS OF ENGINEERS, 1956.

(2) HYDROLOGIC ZONE DEFINED BY CORPS OF ENGINEERS, BALTIMORE DISTRICT, FOR DETERMINATION OF SNYDER COEFFICIENTS (C_p AND C_t).

(3) SNYDER COEFFICIENTS

(4) L = LENGTH OF LONGEST WATERCOURSE FROM DAM TO BASIN DIVIDE

L_{ca} = LENGTH OF LONGEST WATERCOURSE FROM DAM TO POINT OPPOSITE BASIN CENTROID.

L' = LENGTH OF LONGEST WATERCOURSE FROM RESERVOIR INLET TO DRAINAGE DIVIDE.

(5) $t_p = C_t (L \cdot L_{ca})^{0.3}$ or $t_p = C_t (L')^{0.6}$

(6) SERVICE/EMERGENCY

SUBJECT

DAM SAFETY INSPECTIONPICKERAL POND DAM

BY

RJS

DATE

4-13-81

PROJ. NO.

80-238-755


CHKD. BY

DLB

DATE

4-28-81

SHEET NO.

1OF 27Engineers • Geologists • Planners
Environmental SpecialistsDAM STATISTICS

HEIGHT OF DAM = 14 FT (FIELD MEASURED) - TOP OF DAM TO
DOWNSTREAM EMBANKMENT TOE; "TOP OF DAM" HERE AND ON
ALL SUBSEQUENT CALCULATION SHEETS REFERS TO THE MINIMUM
ELEVATION ALONG THE EMBANKMENT CREST.)

NORMAL POOL STORAGE CAPACITY = 362 AC-FT (HEC-1)

MAXIMUM POOL STORAGE CAPACITY = 2796 AC-FT (HEC-1)
(@ TOP OF DAM)

DRAINAGE AREA:

SUB-AREA (SEE FIG. 1)	LOCAL D.A. (SQ. MI.)	CUMULATIVE D.A. (SQ. MI.)
HEMLOCK LAKE	1.1	—
LOWER HEMLOCK LAKE	0.1	1.2
BLUE HERON LAKE	5.0	6.2
PORTERS LAKE	2.7	—
PECKS POND	9.2	—
PICKERAL POND	4.9	23.0

(PLANIMETERED ON USGS TOPO QUADS: PECKS POND,
TWELVEMILE POND, AND PROMISED LAND, PA)

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-13-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 2 OF 27



ELEVATIONS:

TOP OF DAM (DESIGN)	= 1318.0	(FIG. 3; SEE NOTE 1)
TOP OF DAM (FIELD)	= 1317.7	
NORMAL POOL	= 1311.0	(SEE NOTE 1)
SPILLWAY CREST: LOWER STAGE	= 1311.0	(FIELD SURVEY)
UPPER STAGE	= 1311.5	(FIELD SURVEY)
LOW FLOW NOTCH	= 1309.2	(FIELD SURVEY; SEE NOTE 1)
UPSTREAM INLET INVERT (DESIGN)	= 1306.9	(FIG. 3; SEE NOTE 1)
DOWNSTREAM OUTLET INVERT (DESIGN)	= 1306.5	(FIG. 3; SEE NOTE 1)
DOWNSTREAM OUTLET INVERT (FIELD)	= 1305.6	
DOWNSTREAM EMBANKMENT TOE (FIELD)	= 1303.7	
STREAMBED @ DAM CENTERLINE	= 1305	(EST.; FIG. 3, SEE NOTE 1)

NOTE 1: THE DESIGN DRAWINGS ARE BASED ON A NORMAL POOL OR SPILLWAY CREST (LOWER STAGE) ELEVATION OF 92.5. HOWEVER, THE USGS TOPO QUAD FOR PICKS POND, PA, INDICATES THAT THE NORMAL POOL ELEVATION IS 1311. THEREFORE, IT WILL BE ASSUMED THAT THE SPILLWAY CREST (LOWER STAGE) IS AT ELEVATION 1311.0, AND 1218.5 FT (OR 1311.0 - 92.5) WILL BE ADDED TO THE ELEVATIONS GIVEN ON THE DESIGN DRAWINGS. IT IS NOTED THAT THERE ARE TWO LOW-FLOW NOTCHES CUT IN THE SPILLWAY WEIR FOR THE PURPOSE OF PROVIDING A NORMAL POOL ELEVATION SOMEWHAT LOWER THAN THE ORIGINAL NORMAL POOL (LOWER STAGE SPILLWAY CREST, ASSUMED AT EL. 1311.0). HOWEVER, SINCE THE FLOW CAPACITY OF THESE NOTCHES IS SMALL IN COMPARISON TO THAT OF THE SPILLWAY WEIR, THEIR EFFECTS HAVE BEEN NEGLECTED IN THIS ANALYSIS, AND NORMAL POOL IS ASSUMED TO BE AT THE ELEVATION OF THE "LOWER STAGE SPILLWAY CREST." IT IS ALSO NOTED THAT THE ELEVATIONS USED IN THIS ANALYSIS ARE CONSIDERED ESTIMATES, AND ARE NOT NECESSARILY ACCURATE.

DAM CLASSIFICATION

DAM SIZE:	INTERMEDIATE	(REF 1, TABLE 1)
HAZARD CLASSIFICATION:	HIGH	(FIELD OBSERVATION)
REQUIRED SDF:	PMF	(REF 1, TABLE 3)

SUBJECT DAM SAFETY INSPECTIONPICKERAL POND DAMBY DJS DATE 4-13-81 PROJ. NO. 80-238-755CHKD. BY DLB DATE 4-28-81 SHEET NO. 3 OF 27Engineers • Geologists • Planners
Environmental SpecialistsHYDROGRAPH PARAMETERS

$$C_p = 0.45$$

$$C_c = 1.23$$

(SUPPLIED BY C.O.E., ZONE 1,
DELAWARE RIVER BASIN)

SUB-AREA (SEE FIG. 1)	^① L (MI)	^② L _{CA} (MI)	^③ L' (MI)	^④ $t_p = C_c (L \cdot L_{CA})^{0.3}$ (HRS)	^⑤ $t_p = C_c (L')^{0.6}$ (HRS)
HEMOCK LAKE	—	—	0.66	—	0.96
LOWER HEMOCK LAKE	—	—	0.31	—	0.61
BLUE HERON LAKE	4.5	2.4	—	2.51	—
PORTERS LAKE	4.6	1.8	—	2.32	—
PECKS POND	—	—	2.6	—	2.18
PICKERAL POND	3.2	1.8	—	2.08	—

① L = LENGTH OF LONGEST WATERCOURSE.

② L_{CA} = LENGTH OF LONGEST WATERCOURSE FROM DAM TO A POINT
OPPOSITE BASIN CENTROID.③ L' = LENGTH OF LONGEST WATERCOURSE FROM RESERVOIR INLET TO
BASIN DIVIDE; USED IN ESTIMATION OF t_p WHEN RESERVOIR
LENGTH > L_{CA} (AS PER C.O.E., BALTIMORE DISTRICT; STREAM
LENGTHS MEASURED ON USGS TOPO QUADS — PECKS POND, TWELVEMILE
POND, AND PROMISED LAND, PA).

④ FROM REF. 2.

(NOTE: HYDROGRAPH VARIABLES USED HERE ARE DEFINED IN REF. 2,
IN SECTION ENTITLED "SNYDER SYNTHETIC UNIT HYDROGRAPH.")

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
BY DJS DATE 4-13-81 PROJ. NO. 80-238-755
CHKD. BY DLB DATE 4-28-81 SHEET NO. 4 OF 27



RESERVOIR STORAGE CAPACITY

RESERVOIR SURFACE AREAS:

- SURFACE AREA (S.A.) @ NORMAL POOL (EL. 1311.0) = 155 ACRES
- S.A. @ EL. 1320 = 785 ACRES
- S.A. @ EL. 1340 = 1280 ACRES

(PLANIMETERED ON USGS TOPO QUADS - PECKS POND, AND TWELVE MILE POND, PA; PLANIMETERED ONLY AS FAR UPTREAM AS THE PORTERS LAKE WATERSHED BOUNDARY - SEE PORTERS LAKE ANALYSIS (SHEETS 19-21) AND NOTE 6 (SHEET 20).)

- S.A. @ TOP OF DAM (EL. 1317.7) = 624 ACRES

(BY LINEAR INTERPOLATION)

THE "ZERO-STORAGE" ELEVATION IS ASSUMED TO BE AT EL. 1304, APPROXIMATELY THE SAME ELEVATION AS THE DOWNSTREAM TOE OF THE DAM. THE ACTUAL ELEVATION OF THE BOTTOM OF THE RESERVOIR IS UNKNOWN, AND THUS THE VALUE OF 1304 IS USED, SINCE THIS IS THE MAXIMUM LIMIT TO WHICH A POTENTIAL BREACH COULD OCCUR. (THE NORMAL POOL STORAGE CAPACITY COMPRISES ONLY A SMALL PERCENTAGE OF THE MAXIMUM POOL STORAGE CAPACITY.)

ELEVATION - STORAGE RELATIONSHIP:

THE ELEVATION-STORAGE RELATIONSHIP IS COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, BY USE OF THE CONIC METHOD, BASED ON THE GIVEN RESERVOIR SURFACE AREA AND ELEVATION DATA (SEE SUMMARY INPUT/OUTPUT SHEETS).

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY RTS DATE 4-13-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 4-28-81 SHEET NO. 5 OF 27



Engineers • Geologists • Planners
Environmental Specialists

PMP CALCULATIONS

- APPROXIMATE RAINFALL INDEX = 21.5 INCHES
(CORRESPONDING TO A DURATION OF 24 HOURS AND
A DRAINAGE AREA OF 200 SQUARE MILES.)

(REF. 3, FIG. 1)

- DEPTH - AREA - DURATION ZONE 1

(REF. 3, FIG. 1)

- DATA CORRESPONDING TO A 23-SQUARE MILE DRAINAGE AREA:

<u>DURATION (HRS)</u>	<u>PERCENT OF INDEX RAINFALL</u>
6	101
12	114
24	124
48	133

(REF. 3, FIG. 2)

HOP BROOK FACTOR (ADJUSTMENT FOR BASIN SHAPE AND FOR THE
LESSER LIKELIHOOD OF A SEVERE STORM CENTERING OVER A SMALL
BASIN) FOR A DRAINAGE AREA OF 23 SQUARE MILES IS 0.827.

(HEC-1)


SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-14-81 PROJ. NO. 80-238-255
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 6 OF 27

gai
 CONSULTANTS, INC.

Engineers • Geologists • Planners
 Environmental Specialists


SPILLWAY CAPACITY

PROFILE:



CROSS - SECTION:

- LOOKING UPSTREAM -



- SKETCHES BASED ON FIELD SURVEY AND
 DESIGN DRAWINGS.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-14-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 7 OF 27

gai
 CONSULTANTS, INC.
 Engineers • Geologists • Planners
 Environmental Specialists

THE SPILLWAY CONSISTS OF AN UNCONTROLLED RECTANGULAR-SHAPED CONCRETE CHANNEL, WITH DISCHARGES REGULATED BY A TWO-STAGE CONCRETE OGEE-TYPE WEIR, AS SHOWN ON SHEET 6 (SEE NOTES 1 & 2). DISCHARGE OVER THE WEIR CAN BE ESTIMATED BY THE EQUATION

$$Q = CLH^{3/2} \quad (\text{REF 4, p. 373})$$

WHERE Q = DISCHARGE, IN CFS,
 C = COEFFICIENT OF DISCHARGE,
 L = LENGTH OF WEIR CREST,
 H = TOTAL HEAD ON CREST, IN FT.


THE DESIGN HEAD, H_o , IS ASSUMED TO BE 6.9 FT (ABOVE THE LOWER STAGE), OR TO THE TOP OF THE RIGHT SPILLWAY WINGWALL. IT IS ASSUMED THAT THE RELATIONSHIPS IN REF. 4, PP. 372-382, CAN BE APPLIED TO THIS OGEE-LIKE WEIR. FOR AN AVERAGE FOREBAY DEPTH OF ABOUT 2.0 FT,

$$\frac{P}{H_o} = \frac{2.0}{6.9} = 0.29$$

$$\therefore C_o = 3.68 \quad (\text{REF 4, FIG. 249, p. 378})$$

APPROACH CHANNEL LOSSES @ DESIGN HEAD DISCHARGE:

- APPROXIMATION OF AVERAGE CROSS-SECTION OF APPROACH CHANNEL:
 (FROM FIELD NOTES AND FIG. 3)



(NOT TO SCALE)

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-14-81 PROJ. NO. 80-238-755
 CHKD. BY DAB DATE 4-28-81 SHEET NO. 8 OF 27



APPROACH CHANNEL LENGTH (AVG) = 90 FT (FIG 3)

AT ELEV. 1317.9 (ASSUMED DESIGN HEAD),

$$\begin{aligned} \text{FLOW AREA} &= (8.9)(60) + \left(\frac{1}{2}\right)(8.9)(8.9)(15) \\ &= \underline{1128 \text{ FT}^2} \end{aligned}$$

INITIAL ESTIMATE OF DISCHARGE: (SEE NOTE 2)

$$\begin{aligned} Q &= CLH^{3/2} \\ &= (3.68)(83)(6.9)^{3/2} + (3.68)(77)(6.4)^{3/2} \\ &= \underline{10,124 \text{ CFS}} \end{aligned}$$

AVERAGE VELOCITY IN APPROACH CHANNEL:

$$V_A = Q/A = \frac{10,124}{1128} = \underline{9.0 \text{ FT/SEC}}$$

AVERAGE APPROACH VELOCITY HEAD:

$$h_A = \frac{V_A^2}{2g} = \frac{(9.0)^2}{64.4} = \underline{1.26 \text{ FT}}$$

ASSUMING THAT THE APPROACH CHANNEL ENTRANCE LOSS = 0.1 h_A (REF 4, p. 379)

$$h_e = \text{ENTRANCE LOSS} = (0.1)(1.26) = \underline{0.13 \text{ FT.}}$$

APPROACH CHANNEL FRICTION LOSS, h_F :

$$h_F = \left[\frac{V_A n}{(1.486) R^{2/3}} \right]^2 \times L_c \quad (\text{REF 4, p. 379})$$

NOTE 2: THE SPILLWAY CAPACITY IS ESTIMATED BASED ON THE ASSUMPTION THAT THE LOW FLOW NOTCHES IN THE WEIR CAN BE NEGLECTED, AND THAT THE TREES AND BRUSH ARE CLEARED FROM THE LEFT-SIDE PORTION OF THE APPROACH CHANNEL (SEE PHOTO 5).

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS DATE 4-14-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 4-28-81 SHEET NO. 9 OF 27



Engineers • Geologists • Planners
Environmental Specialists

WHERE L_c = LENGTH OF APPROACH CHANNEL = 90 FT (AVG),
 n = MANNING'S ROUGHNESS COEFFICIENT = 0.050
 (TREES AND BRUSH REMOVED)
 R = HYDRAULIC RADIUS = FLOW AREA / WETTED PERIMETER.

$$P_w = \text{WETTED PERIMETER} = 8.9 + 60 + (15.0)(8.9) = \underline{203 \text{ FT}}$$

$$R = \frac{A_p}{P} = \frac{1128}{203} = \underline{5.6 \text{ FT}}$$

$$h_f = \left[\frac{(9.0)(0.050)}{(1.486)(5.6)^{2/3}} \right]^2 \times 90 = \underline{0.83 \text{ FT}}$$

$$\therefore \text{TOTAL APPROACH LOSS} = h_e + h_f \\ = 0.13 + 0.83 = \underline{0.96 \text{ FT}}$$

$$\text{ACTUAL EFFECTIVE HEAD} = 6.9 - 0.96 = \underline{5.94 \text{ FT}}$$

$$\frac{P}{H_o} = \frac{2}{5.94} = \underline{0.34} ; \therefore C_o = \underline{3.72}$$

$$\text{SPILLWAY CAPACITY @ DESIGN HEAD} = 3.72 \left[(83)(5.94)^{3/2} + (77)(5.44)^{3/2} \right] = \underline{8104 \text{ CFS}}$$

FOR HEADS OTHER THAN DESIGN HEAD, THE APPROACH CHANNEL LOSSES WILL BE ASSUMED TO BE PROPORTIONAL TO THE LOSSES AT DESIGN HEAD:

$$h_L = \left(\frac{0.96}{6.9} \right) H$$

WHERE h_L = TOTAL APPROACH CHANNEL LOSS, IN FT,
 AND H = RESERVOIR ELEVATION - 1311.0 FT.

EFFECTS OF HEAD OTHER THAN DESIGN HEAD:

AS THE HEAD ON THE WEIR BECOMES SMALL, DISCHARGE IS REDUCED DISPROPORTIONATELY, DUE TO THE ROUGHNESS AND THE CONTACT

SUBJECT

DAM SAFETY INSPECTIONPICKERAL POND DAM

BY

DJS

DATE

4-14-81

PROJ. NO.

80-238-255

CHKD. BY

DLB

DATE

4-28-81

SHEET NO.

10 OF 27Engineers • Geologists • Planners
Environmental Specialists

PRESSURE BETWEEN THE WATER AND THE WEIR SURFACE. THUS, THE DISCHARGE COEFFICIENT (C) TAKES ON A LOWER VALUE THAN THAT OF DESIGN HEAD. THE OPPOSITE TEND OCCURS FOR HEADS GREATER THAN THAT OF DESIGN. THEREFORE, THE DESIGN DISCHARGE COEFFICIENT WILL BE MODIFIED APPROPRIATELY, ACCORDING TO FIG. 250, REF. 4.

FINALLY, IT WAS ASSUMED THAT THERE WAS NO TAILWATER INTERFERENCE AT THE WEIR.

SPILLWAY RATING CURVE:

(SEE NOTE 2, SHEET 8)

RESERVOIR ELEVATION (FT)	H (FT)	h_L ① (FT)	H_e ② (FT)	H/H_o ③	$\%C_o$ ④	C ⑤	Q ⑥ (CFS)
1311.0	0	-	-	-	-	-	0
1311.5	0.5	0.07	0.43	0.07	0.81	3.01	70
1312.0	1.0	0.14	0.86	0.14	0.84	3.12	260
1313.0	2.0	0.28	1.72	0.29	0.88	3.27	950
1314.0	3.0	0.42	2.58	0.43	0.91	3.39	1950
1315.0	4.0	0.56	3.44	0.58	0.94	3.50	3210
1316.0	5.0	0.70	4.30	0.72	0.96	3.57	4680
1317.0	6.0	0.83	5.17	0.87	0.98	3.65	6400
(TOP OF DAM) 1317.7	6.7	0.93	5.77	0.97	1.00	3.72	7740
(TOP OF WEIRWALL) 1317.9	6.9	0.96	5.94	1.00	1.00	3.72	8100
1318.5	7.5	1.04	6.46	1.09	1.01	3.76	9340
1319.0	8.0	1.11	6.89	1.16	1.02	3.79	10,400
1320.0	9.0	1.25	7.75	1.30	1.04	3.87	12,750
1321.0	10.0	1.39	8.61	1.45	1.05	3.91	15,150
1322.0	11.0	1.53	9.47	1.59	1.07	3.98	17,860
1323.0	12.0	1.67	10.33	1.74	1.07	3.98	20,410
1324.0	13.0	1.81	11.19	1.88	1.07	3.98	23,080
1325.0	14.0	1.95	12.05	2.03	1.07	3.98	25,850

① $h_L = \left(\frac{0.96}{6.9}\right) H$ (SEE SHEET 9)

② $H_e = H - h_L$

③ $H_o = 5.94$

④ FROM REF 4, FIG. 250, p. 378.

⑤ $C_o = 3.72$; $C = 3.72 \times \%C_o$

⑥ $Q = C \left[(83)(H_e)^{3/2} + (77)(H_e - 0.5)^{3/2} \right]$; ROUNDED TO NEAREST 10 CFS.

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS DATE 4-15-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 4-28-81 SHEET NO. 11 OF 27



Engineers • Geologists • Planners
Environmental Specialists

EMBANKMENT RATING TABLE

ASSUME THAT THE EMBANKMENT BEHAVES ESSENTIALLY AS A BROAD-CRESTED WEIR WHEN OVERTOPPING OCCURS. THUS, THE DISCHARGE CAN BE ESTIMATED BY THE RELATIONSHIP

$$Q = CLH^{3/2} \quad (\text{REF 5, p. 5-23})$$

WHERE Q = DISCHARGE OVER EMBANKMENT, IN CFS,
 L = LENGTH OF EMBANKMENT OVERTOPPED, IN FT,
 H = HEAD, IN FT; IN THIS CASE IT IS THE AVERAGE "FLOW AREA WEIGHTED HEAD" ABOVE THE TOP OF THE DAM; AND
 C = COEFFICIENT OF DISCHARGE, DEPENDENT UPON THE HEAD AND THE WEIR BREADTH.

LENGTH OF EMBANKMENT INUNDATED VS. RESERVOIR ELEVATION:

RESERVOIR ELEVATION (FT)	EMBANKMENT LENGTH (FT)
1317.7	0
1317.8	75
1317.9	180
1318.2	180
1318.5	185
1319.0	190
1320.0	195
1321.0	225
1322.0	255
1323.0	285
1324.0	315
1325.0	345

(FROM FIELD SURVEY AND USGS TOPO
QUAD - PECKS POND, PA, AND FIG. 3)

SUBJECT DAM SAFETY INSPECTIONPICKERAL POND DAMBY DJS DATE 4-15-81 PROJ. NO. 80-238-755CHKD. BY DLB DATE 4-28-81 SHEET NO. 12 OF 27Engineers • Geologists • Planners
Environmental Specialists

ASSUME THAT INCREMENTAL DISCHARGES OVER THE EMBANKMENT FOR SUCCESSIVE RESERVOIR ELEVATIONS ARE APPROXIMATELY TRAPEZOIDAL IN CROSS-SECTIONAL FLOW AREA. THEN ANY INCREMENTAL AREA OF FLOW CAN BE ESTIMATED AS $H_i [(L_1 + L_2)/2]$, WHERE L_1 = LENGTH OF EMBANKMENT OVERTOPPED AT HIGHER ELEVATION, L_2 = LENGTH AT LOWER ELEVATION, H_i = DIFFERENCE IN ELEVATIONS. THUS, THE TOTAL AVERAGE "FLOW AREA WEIGHTED HEAD" CAN BE ESTIMATED AS

$$H_w = (\text{TOTAL FLOW AREA} / L_1).$$

EMBANKMENT RATING TABLE:

RESERVOIR ELEVATION	L_1	L_2	INCREMENTAL HEAD, H_i	INCREMENTAL FLOW AREA, A_i	TOTAL FLOW AREA, A_T	WEIGHTED HEAD, H_w	$\frac{H_w}{l}$	C	Q
(FT)	(FT)	(FT)	(FT)	(FT ²)	(FT ²)	(FT)			(CFS)
1317.7	0	—	—	—	—	—	—	—	0
1317.8	75	0	0.1	4	4	0.05	0.005	2.90	0
1317.9	180	75	0.1	13	17	0.09	0.01	2.93	10
1318.2	180	180	0.3	54	71	0.39	0.04	3.01	130
1318.5	185	180	0.3	55	126	0.68	0.06	3.03	310
1319.0	190	185	0.5	94	220	1.2	0.11	3.04	760
1320.0	195	190	1.0	193	413	2.1	0.20	3.07	1820
1321.0	225	195	1.0	210	623	2.8	0.27	3.09	3260
1322.0	255	225	1.0	240	863	3.4	0.32	3.09	4940
1323.0	285	255	1.0	270	1133	4.0	0.38	3.09	7050
1324.0	315	285	1.0	300	1433	4.5	0.43	3.09	9290
1325.0	345	315	1.0	330	1763	5.1	0.49	3.09	12,280

$$\textcircled{1} A_i = H_i [(L_1 + L_2)/2]$$

$$\textcircled{2} H_w = A_T / L_1$$

$$\textcircled{3} l = \text{BREADTH OF CREST} = 10.5 \text{ FT (FIELD MEASURED)}$$

$$\textcircled{4} C = P(H, l); \text{ FROM REF. 12, FIG. 24.}$$

$$\textcircled{5} Q = CL H_w^{3/2} \text{ (ROUNDED TO NEAREST 10 CFS)}$$

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY 255 DATE 4-15-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 13 OF 27



TOTAL FACILITY RATING TABLE

$$Q_{TOTAL} = Q_{SPILLWAY} + Q_{EMBANKMENT}$$

	RESERVOIR ELEVATION (FT)	① Q _{SPILLWAY} (CFS)	② Q _{EMBANKMENT} (CFS)	Q _{TOTAL} (CFS)
(NORMAL POOL)	1311.0	0	—	0
	1311.5	70	—	70
	1312.0	260	—	260
	1313.0	950	—	950
	1314.0	1950	—	1950
	1315.0	3210	—	3210
	1316.0	4680	—	4680
	1317.0	6400	—	6400
(TOP OF DAM)	1317.7	7740	0	7740
	1317.9	8100	10	8110
	1318.2	8720 *	130	8850
	1318.5	9340	310	9650
	1319.0	10,400	760	11,160
	1320.0	12,750	1820	14,570
	1321.0	15,150	3260	18,410
	1322.0	17,860	4940	22,800
	1323.0	20,410	7050	27,460
	1324.0	23,080	9290	32,370
	1325.0	25,850	12,280	38,130

* - BY LINEAR INTERPOLATION.

① FROM SHEET 10.

② FROM SHEET 12.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
BY DJS DATE 4-15-81 PROJ. NO. 80-238-755
CHKD. BY DLB DATE 4-28-81 SHEET NO. 14 OF 27



UPSTREAM DAMS

1) HEMLOCK LAKE DAM:

- DAM STATISTICS :

- HEIGHT OF DAM = 14 FT

(SEE NOTE 3)

- ELEVATION OF NORMAL POOL = 1439.0

"

- ELEVATION OF TOP OF DAM = 1442.0

"

- PMIP DATA - SEE SHEET 5.

- RESERVOIR STORAGE CAPACITY :

(SEE NOTE 3)

<u>ELEV (FT)</u>	<u>STORAGE (AC-FT)</u>
1428.0	0
(NORMAL POOL) 1439.0	918
1440.0	1044
1460.0	4594

- SPILLWAY / EMBANKMENT RATING TABLES :

THE SPILLWAY RATING TABLE AND EMBANKMENT RATING TABLE ARE
COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, BASED ON THE WEIR EQUATION
(SHEETS 7, 11) AND ON THE FOLLOWING INPUT DATA: (SEE NOTE 3)

SPILLWAY: C = 3.3; L = 47 FT; CREST @ EL. 1439.0.

EMBANKMENT: C = 2.6; L = 450 FT; CREST @ EL. 1442.0.

NOTE 3: OBTAINED FROM PHASE I INSPECTION REPORT, NATIONAL DAM
INSPECTION PROGRAM - HEMLOCK LAKE DAM, NDI-PA 00399,
PA DER 52-71, PREPARED BY O'BRIEN AND GETZE, MAY, 1979.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-15-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 15 OF 27



2) LOWER HEMLOCK DAM:

- DAM STATISTICS:

- HEIGHT OF DAM = 15 FT (SEE NOTE 4)
- ELEVATION OF NORMAL POOL = 1432.0 "
- ELEVATION OF TOP OF DAM = 1435.3 "

- PMP DATA - SEE SHEET 5.

- RESERVOIR STORAGE CAPACITY:

THE ELEVATION-STORAGE RELATIONSHIP IS COMPUTED INTERNALLY
 IN THE HEC-1 PROGRAM, BASED ON THE FOLLOWING DATA: (SEE NOTE 4)

<u>ELEV. (FT)</u>	<u>SURFACE AREA (ACRES)</u>
<u>1392.1</u>	<u>0</u>
<u>1432.0</u>	<u>23.1</u>
<u>1440.0</u>	<u>39.7</u>

- FACILITY RATING TABLE:

(SEE NOTE 4)

<u>ELEV. (FT)</u>	<u>OUTFLOW (CFS)</u>	<u>ELEV. (FT)</u>	<u>OUTFLOW (CFS)</u>
<u>1432.0</u>	<u>0</u>	<u>1435.0</u>	<u>877</u>
<u>1432.5</u>	<u>60</u>	(^{TOP} _{DAM}) <u>1435.3</u>	<u>1012</u>
<u>1433.0</u>	<u>169</u>	<u>1436.0</u>	<u>1441</u>
<u>1433.5</u>	<u>310</u>	<u>1436.5</u>	<u>1896</u>
<u>1434.0</u>	<u>477</u>	<u>1437.0</u>	<u>2471</u>
<u>1434.5</u>	<u>667</u>	<u>1438.0</u>	<u>3992</u>

NOTE 4: OBTAINED FROM PHASE I INSPECTION REPORT, NATIONAL
 DAM INSPECTION PROGRAM - LOWER HEMLOCK DAM, NDI-PA 00756,
 PA DER NO. 52-117, PREPARED BY BERGER ASSOCIATES, INC., JUNE 1980.

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS DATE 4-16-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 4-28-81 SHEET NO. 16 OF 27



Engineers • Geologists • Planners
Environmental Specialists

3) BLUE HERON LAKE DAM:

- DAM STATISTICS:

- HEIGHT OF DAM = 11 FT (FIELD MEASURED)
- ELEVATION OF NORMAL POOL = 1337.0 (USGS TOPO - PECKS POND, PA)
- ELEVATION OF TOP OF DAM = 1338.5 (FIELD MEASURED)

- PMP DATA: SEE SHEET 5.

- RESERVOIR STORAGE CAPACITY:

- S.A. @ NORMAL POOL = 90 ACRES
- S.A. @ EL. 1340 = 110 ACRES (PLANIMETERED ON USGS TOPO
- S.A. @ EL. 1360 = 380 ACRES (QUAD - PECKS POND, PA)

S.A. @ TOP OF DAM (EL. 1338.5) = 100 ACRES
(BY LINEAR INTERPOLATION)

VOLUME AT NORMAL POOL = 65×10^6 GALLONS
= 200 AC-FT (SEE NOTE 5)

VOLUME AT NORMAL POOL = $\frac{1}{3} HA = 200$ AC-FT (CONIC METHOD)

WHERE H = MAXIMUM RESERVOIR DEPTH @ NORMAL POOL,

A = SURFACE AREA @ NORMAL POOL = 90 ACRES

$$\therefore H = \frac{(3)(200)}{(90)} = \underline{6.7} \text{ FT}$$

\therefore ZERO STORAGE ASSUMED AT $1337.0 - 6.7 = \underline{1330.3}$

NOTE 5: OBTAINED FROM "DAMS, RESERVOIRS, AND NATURAL LAKES", WATER RESOURCES BULLETIN No. 5, COMMONWEALTH OF PENNSYLVANIA, DEPARTMENT OF FORESTS AND WATER, HARRISBURG, PA, 1970. (BLUE HERON LAKE DAM IS REFERRED TO AS DORYS DAM, PA DER No. 52-9, IN THIS PUBLICATION.)

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
BY RTS DATE 4-16-81 PROJ. NO. 80-238-755
CHKD. BY DLB DATE 4-28-81 SHEET NO. 17 OF 27



BLUE HERON LAKE DAM:

THE ELEVATION-STORAGE RELATIONSHIP IS COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, BASED ON THE SURFACE AREA-ELEVATION DATA GIVEN ON SHEET 16. ALTHOUGH THE MINIMUM RESERVOIR ELEVATION DOES NOT NECESSARILY OCCUR AT EL. 1330.3, THIS VALUE MUST BE USED IN THE HEC-1 INPUT IN ORDER TO MAINTAIN A NORMAL POOL STORAGE OF 200 AC-FT.

SPILLWAY CAPACITY:

THE "SERVICE SPILLWAY" CONSISTS OF A CONCRETE OGEE-TYPE WEIR, WITH AN EFFECTIVE CREST LENGTH OF 24 FT, AND A FREEDBOARD OF 1.5 FT TO THE TOP OF THE DAM (THE FLASHBOARDS, IN PLACE ON THE DATE OF INSPECTION, WERE ASSUMED TO BE REMOVED IN THIS ANALYSIS.)

THE "EMERGENCY SPILLWAY" ALSO CONSISTS OF A CONCRETE OGEE-TYPE WEIR, WITH AN EFFECTIVE CREST LENGTH OF 38 FT, AND A FREEDBOARD OF 1.1 FT TO THE TOP OF THE DAM (I.E. CREST IS AT $1338.5 - 1.1 = 1337.4$).

DISCHARGE OVER EACH WEIR IS ESTIMATED BY THE WEIR EQUATION

$$Q = CLH^{3/2} \quad (\text{SEE SHEET 7}).$$

THE DISCHARGE COEFFICIENT (C) IS ASSUMED TO BE ON THE ORDER OF 3.6 (REF 4). THE TOTAL RATING TABLE FOR THE COMBINED OUTFLOWS OF THE SERVICE AND EMERGENCY SPILLWAYS IS PROVIDED ON SHEET 18.

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS DATE 4-16-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 4-28-81 SHEET NO. 18 OF 27



Engineers • Geologists • Planners
Environmental Specialists

BLUE HERON LAKE DAM:

TOTAL SPILLWAY RATING TABLE:

	ELEVATION (FT)	H_S (FT)	H_E (FT)	Q_{TOTAL} (CFS)
(NORMAL POOL)	1337.0	0	-	0
	1337.4	0.4	0	20
	1338.0	1.0	0.6	150
(TOP OF DAM)	1338.5	1.5	1.1	320
	1339.0	2.0	1.6	520
	1340.0	3.0	2.6	1020
	1341.0	4.0	3.6	1630
	1342.0	5.0	4.6	2320
	1343.0	6.0	5.6	3080
	1344.0	7.0	6.6	3920
	1345.0	8.0	7.6	4820

① $H_S = \text{RESERVOIR ELEVATION} - 1337.0$

② $H_E = \text{RESERVOIR ELEVATION} - 1337.4$

③ $Q = C [L_S H_S^{3/2} + L_E H_E^{3/2}] = 3.6 [(24) H_S^{3/2} + (38) H_E^{3/2}]$

(ROUNDED TO NEAREST 10 CFS)

EMBANKMENT RATING TABLE:

DISCHARGE OVER THE EMBANKMENT WILL BE COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, WITH THE ASSUMPTION THAT CRITICAL DEPTH OCCURS ON THE CREST, AND WITH THE CREST PROFILE REPRESENTED BY A SERIES OF TRAPEZOIDS.

INPUT DATA:

CREST LENGTH: 90 500 500 (ASSUMED)
AT OR BELOW ELEVATION: 1338.5 1340.0 1345.0

(BASED ON FIELD NOTES AND USGS TOP - PICKS POND, PA)

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-16-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 9-28-81 SHEET NO. 19 OF 27



4) PORTERS LAKE DAM:

- DAM STATISTICS:

- HEIGHT OF DAM = 4 FT (FIELD MEASURED)
- NORMAL POOL ELEVATION = 1315.0 (USGS TOPO - PECKS POND, PA)
- ELEVATION OF TOP OF DAM = 1316.5 (FIELD SURVEY)

- PMP DATA: SEE SHEET 5.

- RESERVOIR STORAGE CAPACITY:

S.A. @ NORMAL POOL (EL. 1315.0) = 235 ACRES

S.A. @ EL. 1320 = 310 ACRES

S.A. @ EL. 1340 = 570 ACRES (PLANIMETERED ON USGS TOPO
QUADS - PECKS POND AND
TWELVEMILE POND, PA)

S.A. @ TOP OF DAM (EL. 1316.5) = 258 ACRES
(BY LINEAR INTERPOLATION)

VOLUME @ NORMAL POOL = 623×10^6 GALLONS
= 1900 AC-FT (SEE NOTE 5, SHEET 16)

VOLUME @ NORMAL POOL = $\frac{1}{3} HA = 1900$ AC-FT (CONIC METHOD)

WHERE H = MAXIMUM DEPTH OF RESERVOIR @ NORMAL POOL,
 A = SURFACE AREA @ NORMAL POOL = 235 ACRES.

$$\therefore H = \frac{(3)(1900)}{(235)} = \underline{24.3} \text{ FT}$$

\therefore ZERO STORAGE ASSUMED AT $1315.0 - 24.3 = \underline{1290.7} \text{ FT.}$

THE ELEVATION - STORAGE RELATIONSHIP IS COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, BASED ON THE ABOVE DATA. (SEE SUMMARY INPUT/OUTPUT SHEETS.)


SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 4-17-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 4-28-81 SHEET NO. 20 OF 27



PORTERS LAKE DAM:

SPILLWAY CAPACITY:

THE "SPILLWAY" AT PORTERS LAKE DAM CONSISTS OF WOODEN STOP-LOGS SET BETWEEN CONCRETE PIERS AT THE OUTLET OF WHAT IS ESSENTIALLY A NATURAL LAKE (SEE SKETCH BELOW):



- BASED ON FIELD MEASUREMENTS.

THE SPILLWAY RATING TABLE IS COMPUTED INTERNALLY IN THE HEC-1 PROGRAM, BASED ON THE WEIR EQUATION (SHEET 1), AND ON THE FOLLOWING INPUT DATA:

- $L_{TOTAL} = 3.2 + 3.2 = 6.4$ FT
- ASSUME S IS ON THE ORDER OF 3.3 (SHARP-CRESTED WEIR, REF. 5)
- CREST @ EL. 1315.0 (ASSUME STOP-LOGS KEPT IN PLACE)

NOTE 6: ALTHOUGH THERE WOULD MOST LIKELY BE TAILWATER EFFECTS FROM PICKERAL POND IMMEDIATELY DOWNSTREAM, AND POSSIBLY COMPLETE SUBMERGENCE OF THE DAM UNDER PMF-MAGNITUDE FLOWS, THESE EFFECTS WILL BE NEGLECTED HERE, A CONSERVATIVE ASSUMPTION WITH RESPECT TO THE PICKERAL POND DAM ANALYSIS.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
BY DJS DATE 4-17-81 PROJ. NO. 80-238-755
CHKD. BY DLB DATE 4-28-81 SHEET NO. 21 OF 27



PORTERS LAKE DAM:

- EMBANKMENT RATING TABLE:

DISCHARGE OVER THE EMBANKMENT WILL BE COMPUTED INTERNALLY
IN THE HEC-1 PROGRAM, BASED ON THE ASSUMPTION THAT CRITICAL
DEPTH OCCURS ON THE CREST, AND WITH THE CREST PROFILE REPRESENTED
BY A SERIES OF TRAPEZOIDS. (SEE NOTE 6, SHEET 20)

INPUT DATA:

CREST LENGTH :	80	1400	1400 (ASSUMED)
AT OR BELOW ELEVATION:	1316.5	1320.0	1325.0

(BASED ON FIELD NOTES AND USES TOPO - PECKS POND AND
TOWNEMILE POND, PA)

5) PECKS POND DAM

- DAM STATISTICS:

- HEIGHT OF DAM = 7 FT (SEE NOTE 7)

- ELEVATION OF NORMAL POOL = 1360.0 "

- ELEVATION OF TOP OF DAM = 1362.3 "

- PMP DATA: SEE SHEET 5.

NOTE 7: OBTAINED FROM PHASE I INSPECTION REPORT, NATIONAL DAM
INSPECTION PROGRAM - PECKS POND DAM, NDI No. PA-00754,
PENNSYLVANIA I.D. No. 52-15, PREPARED BY GAI CONSULTANTS, INC.,
JANUARY 1981.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY ZTS DATE 4-17-81 PROJ. NO. 80-238-755
 CHKD. BY DLS DATE 4-28-81 SHEET NO. 22 OF 27



PECKS POND DAM

- RESERVOIR STORAGE CAPACITY:

THE ELEVATION-STORAGE RELATIONSHIP IS COMPUTED
 INTERNALLY IN THE HEC-1 PROGRAM, BASED ON THE FOLLOWING
 DATA: (SEE NOTE 7)

	<u>ELEV. (FT)</u>	<u>SURFACE AREA (ACRES)</u>
	1351.1	0
	1359.2	300
(NORMAL POOL)	1360.0	420
(TOP OF DAM)	1362.3	491
	1380.0	1040

- FACILITY RATING TABLE:

(SEE NOTE 7)

<u>ELEV (FT)</u>	<u>OUTFLOW (CFS)</u>	<u>ELEV (FT)</u>	<u>OUTFLOW (CFS)</u>
1360.0	0	1362.6	590
1360.5	30	1362.7	710
1361.0	100	1363.0	1200
1361.5	200	1363.5	2290
1362.0	320	1364.0	3810
(TOP OF DAM) 1362.3	420	1365.0	7650
1362.4	460	1366.0	12,410
1362.5	530	1367.0	18,130

CURRENT PICKEREL POND DAM

BY: JMS DATE: 5-7-81 SHEET NO: 23 OF 27
 CHKD: JMS DATE: 7-1-81 PROJECT NO: 201230-251


DOWNSTREAM ROUTING SECTIONS

SECTION 1

= 5100 FT D.S. FROM DAM

INVERT = 1260.0

CHANNEL SLOPE = 0.006

 $n_{reg} = 0.080$ $n_{reg} = 0.150$ $n_{ch} = 0.045$ 


SECTION 2

= 6450 FT D.S. FROM DAM

REACH LENGTH = 150 FT

INVERT = 1256.0

CHANNEL SLOPE = 0.006

 $n_{reg} = n_{reg} = 0.100$ $n_{ch} = 0.040$ 


SECTION 3

= 10,650 FT D.S. FROM DAM

REACH LENGTH = 4000 FT

INVERT = 1244.0

CHANNEL SLOPE = 0.003

 $n_{reg} = 0.150$ $n_{reg} = 0.080$ $n_{ch} = 0.045$ 


NOTE: SECTIONS BASED ON FIELD NOTES AND OBSERVATIONS AND
 USGS TOPO QUAD - TWENTYMILE POND, PA. ELEVATIONS ARE
 CONSIDERED ESTIMATES AND ARE NOT NECESSARILY ACCURATE.

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY ZJS DATE 5-1-81 PROJ. NO. 80-238-255


CHKD. BY DLB DATE 5-4-81 SHEET NO. 84 OF 27



Engineers • Geologists • Planners
Environmental Specialists

BREACH ASSUMPTIONS

TYPICAL BREACH SECTION:



HEC-1 DAM BREACHING ANALYSIS INPUT:

(BREACHING ASSUMED TO COMMENCE WHEN RESERVOIR LEVEL REACHES
ELEVATION OF LOW AREA ALONG EMBANKMENT CREST)

<u>PLAN</u>	<u>BREACH BOTTOM WIDTH (FT)</u>	<u>MAX. BREACH DEPTH (FT)</u>	<u>SECTION SIDE-SLOPES</u>	<u>BREACH TIME (HRS)</u>
① MIN. BREACH SECTION MIN. FAIL TIME	0	14	1H:1V	0.5
② MAX. BREACH SECTION MIN. FAIL TIME	100	14	2.5:1	0.5
③ MIN. BREACH SECTION MAX. FAIL TIME	0	14	1:1	4.0
④ MAX. BREACH SECTION MAX. FAIL TIME	100	14	2.5:1	4.0
⑤ AVERAGE POSSIBLE CONDITIONS	40	14	1:1	1.0

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DATE

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-4-81

SHEET NO.

25

OF

27



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

THE BREACH ASSUMPTIONS LISTED ON THE PRECEDING SHEET ARE BASED ON THE SUGGESTED RANGES PROVIDED BY THE C.O.E. (BALTIMORE DISTRICT), AND ON THE PHYSICAL CONSTRAINTS OF THE DAM AND SURROUNDING TERRAIN:

- DEPTH OF BREACH OPENING = 14 FT (HEIGHT OF DAM - SEE SHEET 1)
- LENGTH OF BREACHABLE EMBANKMENT = 175 FT (FIELD MEASURED)
- VALLEY BOTTOM WIDTH = 250 - 300 FT (FIELD OBSERVATION;
INCLUDES SPILLWAY)
- VALLEY SIDE-SLOPES ADJACENT TO DAM:
 - RT. ABUTMENT: = 7H:1V (FIG. 3)
 - LT. ABUTMENT: = 5H:1V "

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 5-5-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 5-11-81 SHEET NO. 26 OF 27



HEC-1 DAM BREACHING ANALYSIS OUTPUT SUMMARY:

RESERVOIR DATA: (UNDER 0.42 PMF CONDITIONS)

PLAN #	VARIABLE BREACH BOTTOM WIDTH (FT)	ACTUAL MAX. FLOW DURING FAIL TIME (CFS)	CORRESPONDING TIME OF PEAK (HRS)	INTERPRETED OR HEC-1 ROUTED MAX. FLOW DURING FAIL TIME (CFS)	CORRESPONDING TIME OF PEAK (HRS)	ACTUAL PEAK FLOW THROUGH DAM (CFS)	CORRESPONDING TIME OF PEAK (HRS)	TIME OF INITIAL BREACH (HRS)
①	0	9713	45.50	9713	45.50	9713	45.50	45.00
②	100	26,220	45.50	26,220	45.50	26,220	45.50	45.00
③	0	8579	48.58	8579	48.58	8579	48.50	45.00
④	100	15,274	48.67	15,274	48.67	15,274	48.67	45.00
⑤	40	15,300	46.00	15,300	46.00	15,300	46.00	45.00

* - SEE SHEET 24.

(THE ADV-BREACH 0.42 PMF PEAK OUTFLOW = 8253 CFS)

SUBJECT DAM SAFETY INSPECTIONPICKERAL POND DAMBY DJS DATE 5-5-81 PROJ. NO. 80-238-255CHKD. BY DLG DATE 5-11-81 SHEET NO. 27 OF 27Engineers • Geologists • Planners
Environmental SpecialistsDOWNSTREAM ROUTING DATA:

(UNDER 0.42 PMF BASE FLOW CONDITIONS)

PLAN *	PEAK FLOW (CFS)	CORRESPONDING WATER SURFACE ELEVATION (FT)	WATER SURFACE ELEVATION W/O BREACH (FT)	ELEVATION DIFFERENCE (FT)	ESTIMATED DAMAGE ELEVATION (FT)
OUTPUT @ SECTION 1:					
①	9593	1270.3	1269.7	+0.6	1265
②	22,882	1274.5	1269.7	+4.8	
③	8577	1269.8	1269.7	+0.1	
④	15,225	1272.4	1269.7	+2.7	
⑤	14,412	1272.1	1269.7	+2.4	
OUTPUT @ SECTION 2:					
①	9595	1264.5	1264.0	+0.5	1262
②	22,894	1268.6	1264.0	+4.6	
③	8576	1264.1	1264.0	+0.1	
④	15,226	1266.4	1264.0	+2.4	
⑤	14,414	1266.2	1264.0	+2.2	
OUTPUT @ SECTION 3:					
①	9481	1253.8	1253.3	+0.5	1249
②	20,916	1256.9	1253.3	+3.6	
③	8568	1253.5	1253.3	+0.2	
④	15,070	1255.5	1253.3	+2.2	
⑤	13,796	1255.2	1253.3	+1.9	

* - SEE SHEET 24.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY DJS DATE 5-17-81 PROJ. NO. 80-238-755
 CHKD. BY DAB DATE 5-13-81 SHEET NO. A OF DD



SUMMARY INPUT/OUTPUT SHEETS

DAM SAFETY INSPECTION
 PICKERAL POND DAM 95 OVERTOPPING ANALYSIS 95 (U.S. DAMS INCLUDED)
 10-MINUTE TIME STEP AND 48-HOUR STORM DURATION

NO	NHR	NRH	1DAY	1HR	1MIN	METRC	IPLT	IPRT	INSTAN
300	0	10	0	0	0	0	0	0	0
			JOPER	NWT	LHUP	TRACE			
			5	0	0	0			

OVERTOPPING ANALYSIS

MULTI-PLAN ANALYSES TO BE PERFORMED
 MPPLAN=1 MPTION=3 LRTION=1

RTIOS= .40 .50 1.00

LOCAL INFLOW=PECKS POND

ISTAO	1COMP	IECON	ITAPE	JPLT	JPRT	IMANE	ISTAGE	IAUTO
PEPD	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INIDC	1ONG	TAREA	SNAP	TRSPC	RATIO	ISHOW	ISAME	LOCAL
1	9.20	0.00	23.00	0.00	0.000	0	1	0

PRECIP DATA

SPPE	PMS	H6	R12	R24	R48	H72	H96
0.00	21.50	101.00	114.00	124.00	133.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .827

LOSS DATA

LROPT	STRES	OLTR	RTIOI	ERAIN	STRES	RTIOK	STRTL	CNSTL	ALSHK	HTMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
 TP= 2.16 CP= .45 MTA= 0 BASE FLOW PARAMETERS
 INITIAL & CONSTANT RAINFALL
 LOSSES AS PER C.O.E.

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SYNDET CP AND TP ARE TC=13.40 AND H=20.83 INTERVALS

RECESSION DATA

SINTOS	-1.50	ORSHZ	-1.05	RTIORE	2.00
UNIT HYDROGRAPH100	END-OF-PERIOD	ORDINATES, (AGE	2.19	HOURS, CP=	.45
24.	184.	297.	424.	561.	708.
1166.	1225.	1255.	1244.	1196.	1140.
847.	855.	815.	776.	740.	705.
555.	579.	504.	450.	436.	416.
393.	312.	297.	283.	270.	257.
212.	202.	193.	184.	175.	167.
131.	125.	119.	114.	104.	94.
87.	77.	74.	70.	67.	64.
50.	46.	44.	42.	40.	38.
31.	30.	28.	27.	26.	24.
					23.
					22.
					21.
					20.
					19.
					18.
					17.
					16.
					15.
					14.
					13.
					12.
					11.
					10.
					9.
					8.
					7.
					6.
					5.
					4.
					3.
					2.
					1.
					0.

RAIN EXCS LUBS CUMP 0
 SUM 23.66 21.26 2.40 106359.
 (601.31 940.31 (61.31) (19945.23)

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DJS

DATE

5-11-81

PROJ. NO.

80-238-755

CHKD. BY

DAB

DATE

5-13-81

SHEET NO.

B OF 22



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

0.40 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4953.	1915.	937.	281233.
CMS	140.	54.	27.	7964.
INCHES	5.01	1.75	0.88	7.90
AC-FT	127.19	190.78	200.63	200.63
THOUS CU M	3029.	4686.	4778.	4778.

0.50 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	8001.	3194.	1172.	351541.
CMS	227.	88.	41.	9955.
INCHES	6.26	2.46	0.87	9.87
AC-FT	198.59	245.94	250.79	250.79
THOUS CU M	3070.	4749.	4842.	4842.
	3787.	5837.	5973.	5973.

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	16002.	4788.	2344.	703082.
CMS	453.	136.	66.	19909.
INCHES	12.52	19.37	19.75	19.75
AC-FT	317.59	491.89	501.58	501.58
THOUS CU M	6140.	9497.	9684.	9684.
	7873.	11715.	11945.	11945.

HYDROGRAPH ROUTING

ROUTE THROUGH PECKS POND DAM

STAGE	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTU
PEPD	1	0	0	0	0	1	0	0

ROUTING DATA

QLOSS	CLOSS	AVG	IRIS	ISANE	IOPI	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

MSIPS	MSDOL	LAG	ANSKA	X	TSK	STUWA	ISPRAT
1	0	0	0.000	0.000	0.000	1097.	-1

STAGE	1360.00	1360.50	1361.00	1361.50	1362.00	1362.30	1362.40	1362.50	1362.60
	1363.00	1363.50	1364.00	1365.00	1365.00	1367.00			
FLOW	0.00	30.00	100.00	200.00	320.00	420.00	460.00	510.00	590.00
	1200.00	2290.00	3810.00	7650.00	12410.00	18130.00			

SURFACE AREA

0. 300. 420. 491. 1040.

CAPACITY

0. 810. 1097. 2143. 15392.

ELEVATION

1351. 1359. 1360. 1362. 1380.

CHPL	SP410	CUH	EXP	ELEV	CUUL	CAREA	L4PL
1360.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

TUPEL	CUH	EXP	DARWID
1362.3	0.0	0.0	0.0

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY 205

DATE 5-12-81

PROJ. NO. 80-238-755

CHKD. BY DLG

DATE 5-13-81

SHEET NO. C OF 22



CONSULTANTS, INC.

**Engineers • Geologists • Planners
Environmental Specialists**

0.40 PMF

0.50 PMF

PLZF

PECKS POND -
OUTFLOW.

	PEAK	6-MUVR	24-MUVR	72-MUVR	TOTAL VOLUME
CSB	4217.	3940.	1157.	556.	166919.
CBS	119.	100.	31.	16.	4727.
10CHES		3.58	4.68	4.69	4.69
NA		90.92	110.82	119.08	119.08
ACPT		3799.	2299.	2299.	2299.
7MUVR CU-N		2185.	2030.	2036.	2036.

	PEAK	8-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	5816.	4839.	1693.	771.	23224.
CMS	165.			22.	6548.
INCHES		4.89	6.48		6.49
MM		124.27	164.63	164.96	164.96
AC-FY			3179.	3105.	3185.
TROUGH CU M		2900.	3921.	3929.	3929.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFA	1352.	1139.	3877.	1869.	95971.
CMS	381.		110.	53.	15037.
INCHES		11.25	35.68	15.71	15.71
MM		285.85	398.33	398.99	398.99
AC-FI		5519.	7631.	7703.	7703.
THOUS CU M		6008.	9407.	9502.	9502.

100

SUB-AREA RUNOFF COMPUTATION

ISTAO	ICOMP	I ECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IANTU
0	0	0	7	0	0	.	.	.
0	0	0	7	0	0	.	.	.

HYDROGRAPH DATA		RATIO		ISANE		LOCAL	
INTOC	IUNC	TAREA	SNAP	TRSDA	TRSPC	ISNOW	ISDCL
1	1	1.10	0.00	23.00	0.00	0	0

SPFL	PMS	R6	R12	R24	R48	R72	R96
0.00	21.50	101.00	114.00	124.00	133.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS - 0.00

LOSS DATA										
LNROPT	STAKE	DLTRN	RTIOL	ERRIN	STKKS	RTYON	STATS	CNSTL	ALSNX	RTTMS
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
CP= .96 CPZ = .45 NTZ = 0

APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SWIDER CP AND TP ARE TCE= 6.03 AND R9.29 INTERVALS

RECESSION DATA		
SIRTO=	-1.50	RTION= 2.00
UNCSN=	-.05	

UNIT HYDROGRAPH 53 END-OF-PERIOD ORIGINATES, IAG=					.97 HOURS, CP=	.45	VOL=1.00
21.	77.	156.	239.	302.	332.	319.	287.
006.	187.	167.	210.	133.	121.	109.	258.
71.	64.	57.	51.	46.	37.	98.	79.
24.	22.	19.	17.	16.	14.	30.	27.
0.	7.	7.	6.	5.	5.	11.	10.
3.	3.	2.				4.	3.

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DSS

DATE

5-12-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81

SHEET NO.

D OF DD



Engineers • Geologists • Planners
Environmental Specialists

0.40PMF

0.50PMF

PMF

PERIOD RAIN EXCS LOSS CUMPD
SUN 21.66 21.26 2.40 89969.
(601.11 540.11 61.)(2547.64)

HEMLOCK
LAKE -
INFLOW.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1192.	725.	245.	120.	35976.
34.	21.	7.	3.	1019.
	6.13	8.27	8.45	8.45
	155.72	210.14	214.66	214.66
AC-FT	359.	485.	496.	496.
THOUS CU M	443.	598.	611.	611.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1499.	906.	306.	150.	49970.
42.	28.	9.	4.	1273.
	7.66	10.34	10.56	10.56
	194.65	262.67	268.32	268.32
AC-FT	449.	608.	619.	619.
THOUS CU M	554.	744.	764.	764.

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
2919.	1812.	611.	300.	89940.
84.	51.	17.	8.	2547.
	15.33	20.68	21.13	21.13
	309.30	525.35	536.64	536.64
AC-FT	899.	1213.	1239.	1239.
THOUS CU M	1109.	1496.	1528.	1528.

HYDROGRAPH ROUTING

ROUTE THROUGH HEMLOCK LAKE DAM

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRT	IVAME	ISTAGE	IAUTU
MLD	1	0	0	0	0	1	0	0
ROUTING DATA								
GLASS	CLASS	AVG	IRIS	ISAME	IUPT	IPMP	LASTH	
0.0	0.00	0.00	1	1	0	0	0	
MSIPS	MSIDL	LAG	ANSEK	X	TSK	STORA	ISPRAT	
1	0	0	0.000	0.000	0.000	-1439.	0	

CAPACITY=

0. 918. 1044. 4594.

ELEVATIONS

1028. 1439. 1440. 1460.

CREL	SPRID	COUV	ELPM	ELEV	COOL	CAREA	EXPL
1439.0	47.0	3.3	1.5	0.0	0.0	0.0	0.0

DAM DATA

TOPEL	COON	EXPD	DAMRID
1442.0	2.6	1.5	450.

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS

DATE

5-12-81

PROJ. NO.

80-238-755

CHKD. BY DLB

DATE

5-13-81

SHEET NO.

E OF 20



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

0.40PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
427.	303.	156.	75.	22631.
12.	11.	4.	2.	641.
	3.24	5.29	5.32	5.32
	82.32	134.31	135.03	135.03
	190.	310.	312.	312.
	234.	302.	304.	304.

HEMLOCK
LAKE -
OUTFLOW.

0.50PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
555.	494.	201.	97.	29106.
16.	14.	6.	3.	824.
	4.18	6.80	6.84	6.84
	106.18	172.67	173.66	173.66
	245.	399.	401.	401.
	302.	492.	495.	495.

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1791.	1242.	400.	222.	66659.
51.	35.	13.	6.	1888.
	10.51	15.56	15.66	15.66
	288.83	392.18	397.79	397.79
	516.	912.	918.	918.
	760.	1125.	1133.	1133.

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW - LOWER HEMLOCK LAKE

ISTAO	ICOMP	ILCON	ITAPE	JPLT	JPRF	INAME	ISTAGE	LAUTO
0	0	0	0	0	0	1	0	0

INTUG	INTUG	AREA	SNAP	TRSDA	TRSPC	HA110	ISMDR	ISAME	LOCAL
1	1	.10	0.00	23.00	0.00	0.000	0	1	0

SPFE	PMS	R6	R12	R24	R48	R72	R96
0.00	21.50	101.00	114.00	124.00	133.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .827

LRDPT	STRM	D1TR	RTIUL	ERAIN	SYRKS	RTIUR	STRTL	CNSTL	ALSMI	RTIAP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
TP= .61 CP= .45 RTA= 0

RECESSION DATA	SINTON	-1.50	URCSM	-.05	RTIUR	2.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SYNTER CP AND TP ARE TC= 3.71 AND N= 5.97 INTERVALS						

UNIT HYDROGRAPH 34 END-UP-PERIOD ORIGINATED, LAGE	.61 HOURS, CP=	.45	VOL=	1.00
6.	22.	39.	46.	42.
16.	13.	11.	9.	8.
3.	2.	2.	1.	1.
1.	0.	0.	0.	0.

MAIN	EXCS	LOSS	CUMF	Q
SUN	23.66	21.26	2.40	W200.
(601.1)	(540.1)	(61.1)	(232.20)	

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS

DATE

5-12-81

PROJ. NO.

80-238-755CHKD. BY DLB

DATE

5-13-81

SHEET NO.

F OF 20Engineers • Geologists • Planners
Environmental Specialists

0.40 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
137.	70.	22.	11.	3284.
CFS	2.	1.	0.	93.
INCHES	6.51	8.30	8.49	8.49
MM	165.27	210.74	215.86	215.86
AC-FT	38.	44.	45.	45.
THOUS CU Y	43.	55.	56.	56.

0.50 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
171.	87.	28.	14.	4105.
CFS	5.	1.	0.	116.
INCHES	8.13	10.37	10.61	10.61
MM	206.59	263.43	269.45	269.45
AC-FT	43.	55.	57.	57.
THOUS CU Y	51.	68.	70.	70.

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
342.	175.	96.	37.	9211.
CFS	10.	5.	1.	233.
INCHES	16.27	20.74	21.22	21.22
MM	413.37	526.86	538.89	538.89
AC-FT	87.	111.	113.	113.
THOUS CU Y	107.	136.	140.	140.

COMBINE HYDROGRAPHS

COMBINE HEMLOCK LAKE DAM OUTFLOW W/ LOWER HEMLOCK LAKE INFLOW

ISPU	ICOMP	IECUN	ISAPE	JPLI	JPRI	INAME	ISTACK	IAUTO
2	0	0	0	0	0	1	0	0

SUM OF HEMLOCK
LAKE DAM
OUTFLOW AND
LOWER HEMLOCK
LAKE LOCAL
INFLOW.

0.40 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
456.	414.	179.	96.	25915.
CFS	12.	5.	2.	734.
INCHES	3.21	5.54	5.58	5.58
MM	81.66	100.88	141.74	141.74
AC-FT	265.	384.	387.	387.
THOUS CU Y	293.	437.	440.	440.

0.50 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
593.	534.	229.	111.	33211.
CFS	17.	6.	3.	940.
INCHES	4.14	7.10	7.15	7.15
MM	105.07	180.23	181.65	181.65
AC-FT	265.	454.	457.	457.
THOUS CU Y	326.	560.	564.	564.

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1924.	1348.	516.	250.	7480.
CFS	50.	15.	7.	2120.
INCHES	10.45	15.99	16.12	16.12
MM	265.35	406.13	409.85	409.85
AC-FT	648.	1023.	1031.	1031.
THOUS CU Y	824.	1262.	1272.	1272.

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY JTS DATE 5-12-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 5-13-81 SHEET NO. 6 OF 22



HYDROGRAPH ROUTING

ROUTE TOTAL HYDROGRAPH THROUGH LINER HEMLOCK LAKE DAM

STAGE	1432.00	1432.50	1433.00	1433.50	1434.00	1434.50	1435.00	1435.30	1436.00
FLOW	0.00	60.00	165.00	310.00	477.00	667.00	877.00	1012.00	1441.00
2471.00	3992.00								
SURFACE AREA=	0.	23.	40.						
CAPACITY=	0.	307.	353.						
ELEVATION=	1392.	1432.	1440.						

CHSL SPNID COOW EXPW ELEV. CUOL CANEA EXPL
 1432.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

TUPEL CUOW EXPD DAMWID
 1435.3 0.0 0.0 0.0

LOWER
HEMLOCK
DAM -
OUTFLOW.

0.40 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
438.	402.	162.	78.	23517.
12.	11.	5.	2.	666.
CFS	3.11	5.03	5.06	5.06
INCHES	79.12	127.81	128.63	128.63
MM	199.	322.	324.	324.
AC-FT	246.	397.	400.	400.
THOUS CU N				

0.50 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
571.	519.	210.	101.	30431.
16.	15.	6.	3.	662.
CFS	4.03	6.51	6.55	6.55
INCHES	102.26	163.36	166.44	166.44
MM	250.	416.	419.	419.
AC-FT	310.	514.	517.	517.
THOUS CU N				

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
1046.	1319.	490.	237.	70972.
52.	37.	14.	7.	2010.
CFS	10.22	15.10	15.20	15.20
INCHES	259.65	385.37	388.10	388.10
MM	656.	971.	978.	978.
AC-FT	807.	1198.	1206.	1206.
THOUS CU N				

SUBJECT

DAM SAFETY INSPECTION
PICKERAL POND DAMBY DJSDATE 5-12-81

PROJ. NO.

80-238-755CHKD. BY DLBDATE 5-13-81

SHEET NO.

H OF 20Engineers • Geologists • Planners
Environmental Specialists

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW - BLUE HERON LAKE

INSTAU	ICUM	ITAPE	JPLI	JPRF	ISAGE	IAUTO
0	0	0	0	0	1	0

INTUG	IUNG	TAREA	SNAP	THSUA	THSPC	RATIO	ISMUN	ISAME	LICAL
1	1	5.00	0.00	23.00	0.00	0.000	0	1	0

SPFE	PMS	R6	R12	R24	R72	R96
0.00	21.50	101.00	114.00	124.00	133.00	0.00

THSPC COMPUTED BY THE PROGRAM IS .027

LOSS DATA	STRAK	STNKS	NTIUK	STNKL	CHSTL	ALSMX	HTIUP
0	0.00	0.00	1.00	1.00	.05	0.00	0.00

UNIT HYDROGRAPH DATA
TPA 2.51 CP= .45 RTAN 0APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SKEWER CP AND TP ARE TC=15.57 AND R=23.00 INTERVALS
STMT0= -1.50 ONCSM= -.05 RTIUM= 2.00

UNIT HYDROGRAPH END-OF-PERIOD ORDINATES: LAGS	2.52 HOURS	CP= .45	VDLA	.98
9.	39.	72.	116.	231.
500.	530.	540.	590.	591.
483.	443.	426.	408.	391.
317.	304.	291.	278.	264.
200.	191.	184.	176.	169.
137.	131.	126.	118.	111.
90.	86.	83.	79.	73.
59.	57.	54.	50.	46.
39.	37.	36.	31.	30.
25.	24.	23.	22.	21.
				20.
				19.
				18.
				17.
				16.
				15.
				14.
				13.
				12.
				11.
				10.
				9.
				8.
				7.
				6.
				5.
				4.
				3.
				2.
				1.
				0.

RAIN EGS LOSS CUM P

SUM 23.46 21.26 2.40 37113.
(601.31 540.31 61.11 10500.78)LOCAL INFLOW -
BLUE HERON
LAKE DAM.

THOUS CU M	AC-FT	INCHES	CM	FEET	THOUS CU M	AC-FT	INCHES	CM	FEET
9.	39.	72.	116.	231.	9.	39.	72.	116.	231.
500.	530.	540.	590.	591.	500.	530.	540.	590.	591.
483.	443.	426.	408.	391.	483.	443.	426.	408.	391.
317.	304.	291.	278.	264.	317.	304.	291.	278.	264.
200.	191.	184.	176.	169.	200.	191.	184.	176.	169.
137.	131.	126.	118.	111.	137.	131.	126.	118.	111.
90.	86.	83.	79.	73.	90.	86.	83.	79.	73.
59.	57.	54.	50.	46.	59.	57.	54.	50.	46.
39.	37.	36.	31.	30.	39.	37.	36.	31.	30.
25.	24.	23.	22.	21.	25.	24.	23.	22.	21.
				20.					20.
				19.					19.
				18.					18.
				17.					17.
				16.					16.
				15.					15.
				14.					14.
				13.					13.
				12.					12.
				11.					11.
				10.					10.
				9.					9.
				8.					8.
				7.					7.
				6.					6.
				5.					5.
				4.					4.
				3.					3.
				2.					2.
				1.					1.
				0.					0.

0.40 PMF

0.50 PMF

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DRS DATE 5-12-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 5-13-81 SHEET NO. I OF 22



Engineers • Geologists • Planners
Environmental Specialists

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
8082.	6402.	2622.	1234.	310264.
328.	101.	71.	35.	10485.
INCHES	11.91	10.77	19.14	19.14
MM	302.83	476.78	486.03	486.03
AC-FT	3175.	5003.	5100.	5100.
THOUS CU M	3916.	6171.	6291.	6291.

COMBINE HYDROGRAPHS

CUMULATIVE BLUE HERON LAKE INFLOW W/ LOWER HEMLOCK LAKE DAM OUTFLOW

ISTAU ICUMP ILCUM ITAPE JPLT JPRT IMANE ISTAGE IAUU
MHD 2 0 0 0 0 0 0 0

SUM OF BLUE
HERON LAKE
LOCAL INFLOW
AND LOWER LAKE
HEMLOCK LAKE
OUTFLOW.

0.40PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
3800.	2033.	1171.	572.	171623.
182.	83.	33.	16.	4880.
INCHES	4.46	7.03	7.15	7.15
MM	111.77	170.54	181.60	181.60
AC-FT	1484.	2223.	2364.	2364.
THOUS CU M	1794.	2865.	2916.	2916.

0.50PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
4524.	2486.	1471.	719.	215563.
128.	104.	42.	20.	6104.
INCHES	5.63	8.43	8.98	8.98
MM	140.48	224.35	228.19	228.19
AC-FT	1828.	2918.	2969.	2969.
THOUS CU M	2255.	3699.	3662.	3662.

PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
9744.	7091.	3012.	1071.	41230.
276.	216.	85.	42.	12494.
INCHES	11.54	10.08	10.39	10.39
MM	293.10	459.12	467.09	467.09
AC-FT	3814.	5974.	6078.	6078.
THOUS CU M	4704.	7369.	7497.	7497.

HYDROGRAPH ROUTING

ROUTE TOTAL HYDROGRAPH THROUGH BLUE HERON LAKE DAM

ISTAU ICUMP ILCUM ITAPE JPLT JPRT IMANE ISTAGE IAUU
MHD 1 0 0 0 0 0 0 0

ALL PLANS HAVE SAME

CLASS	CLASS	AVG	INCS	ISANE	IOPT	IPAP	IPAP	LASTH
6.0	0.000	0.00	1	1	0	0	0	0
MSPS	MSDUL	LAC	ANSKE	Z	TSA	STUNA	ISPRAT	-1
1	0	0	0.000	0.000	0.000	-1337.	-1	

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DRS DATE 5-12-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 5-13-81 SHEET NO. J OF 20



Engineers • Geologists • Planners
Environmental Specialists

STAGE	1337.00	1338.00	1339.00	1340.00	1341.00	1342.00	1343.00
FLOW	0.00	28.00	150.00	320.00	520.00	1020.00	2080.00
SURFACE AREA	0.	90.	100.	110.	380.		
CAPACITY	0.	201.	343.	501.	9131.		
ELEVATION	1330.	1337.	1339.	1340.	1360.		

CREST SPREAD COOR EXPO ELEV COOL CAREA EXPL
1337.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAM DATA
TUPEL CUON EXPO DAMMED
1338.5 0.0 0.0 0.

CREST LENGTH 90. 800. 900.
AT OR BELOW ELEVATION 1330.5 - 1340.0 - 1343.0

0.40 PMF

0.50 PMF

PMF

PEAK	3325	2083	1071	575	15441
CFS	100.	82.	39.	19.	4287.
INCHES	109.98	6.33	6.43	6.46	6.46
MM	1430.	163.33	164.02	164.02	164.02
AC-FT	1430.	2125.	2134.	2134.	2134.
THOUS CU N	1768.	2621.	2632.	2632.	2632.

PEAK	3403	1307	659	197607
CFS	126.	103.	19.	5597.
INCHES	5.46	8.20	8.24	8.24
MM	138.40	204.34	209.25	209.25
AC-FT	1806.	2711.	2723.	2723.
THOUS CU N	2228.	3364.	3358.	3358.

PEAK	9619	7647	2890	419156
CFS	273.	217.	82.	11069.
INCHES	31.07	17.34	17.47	17.47
MM	291.41	440.56	443.72	443.72
AC-FT	3792.	5732.	5773.	5773.
THOUS CU N	4677.	7071.	7122.	7122.

BLUE HERON LAKE
DAM OUTFLOW.

SUB-AREA RUNOFF COMPUTATION									
LOCAL INFLOW - PORTERS LAKE									
INTG	INTG	YAREA	SNAP	TRSD	TRSD	RATIO	TRSD	TRSD	LOCAL
1	1	2.70	0.00	23.00	0.00	0.000	0	1	0
ISTAG	ICOMP	IECON	ITAPE	JPLT	JPRF	IRANE	ISTAGE	IAUTO	
PLD	0	0	0	0	0	1	0	0	


HYDROGRAPH DATA

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DES DATE 5-12-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 5-13-81 SHEET NO. K OF 222



Engineers • Geologists • Planners
Environmental Specialists

PRECIP DATA
DATE 0.00 21.50 101.00 114.00 136.00 133.00 0.00 0.00
TIME 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00
TRPC COMPUTED BY THE PROGRAM IS .027

LOSS DATA
DATE 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00
TIME 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00
UNIT HYDROGRAPH DATA
TP= 2.32 CP= .45 RTA= 0

RECESSION DATA
START= -1.50 ORCEN= -.05 RTOR= 2.00
APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNIDER CP AND TP ARE TC=14.46 AND R=22.01 INTERVALS


UNIT HYDROGRAPH 100 END-UP PERIOD ORIGINATES. LAG= 2.32 HOURS, CP= .45 VOL= .99			
6.	23.	47.	76.
320.	343.	369.	394.
251.	269.	289.	310.
160.	152.	146.	139.
101.	91.	82.	88.
64.	61.	59.	56.
41.	38.	37.	34.
26.	25.	24.	23.
16.	16.	15.	14.
10.	10.	10.	9.
			8.
			7.
			6.
			5.
			4.
			3.
			2.
			1.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.
			0.

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY RTS DATE 5-12-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 5-13-81 SHEET NO. 4 OF 22



Engineers • Geologists • Planners
Environmental Specialists

ROUTE THROUGH PORTERS LAKE DAM

HYDROGRAPH ROUTING

ISTAU	ICUMP	SECUN	ITAPE	JPLT	JPRY	INAME	ESTAGE	IAUTD
PLD	1	0	0	0	0	1	0	0
ROUTING DATA	GROSS	CROSS	AVG	INLS	ISANE	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0	0
MSPTS	MSDOL	LAG	ANSKE	X	TRK	STURA	ISPRAT	0
1	0	0	0.000	0.000	0.000	-1315.	0	0

SURFACE AREA	0.	235.	258.	310.	570.
CAPACITY	0.	1004.	2273.	3266.	11935.
ELEVATIONS	1291.	1315.	1317.	1320.	1300.

CHSL	SPWD	CUON	CAPO	ELEV.	LINE	CANEA	EXPL
1315.0	0.4	3.3	1.5	0.0	0.0	0.0	0.0

DAM DATA	TOPEL	COORD	ELEV	DAMNID
	1316.5	0.0	0.0	0.

CREST LENGTH	00.	1400.	1400.
AT OR BELOW			
ELEVATION	1316.5	1320.0	1325.0

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1034.	079.	265.	30120.
CHS	29.	25.	7.	1079.
INCHES	3.03	3.65	3.65	3.65
AC-FT	76.89	92.62	92.66	92.66
THOUS CU N	436.	325.	325.	325.
	537.	647.	648.	648.

PORTERS
LAKE -
OUTFLOW.

0.40 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1036.	1267.	393.	56604.
CHS	43.	36.	11.	1605.
INCHES	4.36	5.42	5.42	5.42
AC-FT	110.85	137.73	137.79	137.79
THOUS CU N	628.	780.	781.	781.
	778.	963.	963.	963.

0.50 PMF

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1037.	3213.	1058.	152452.
CHS	114.	91.	30.	4217.
INCHES	11.07	14.50	14.50	14.50
AC-FT	281.14	370.43	370.59	370.59
THOUS CU N	1593.	2099.	2100.	2100.
	1965.	2580.	2590.	2590.

PMF

PORTERS
LAKE -
OUTFLOW.

0.40PMF

0.50PMF

PMF

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

RJS

DATE

5-12-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81

SHEET NO.

M

OF

222



Engineers • Geologists • Planners
Environmental Specialists

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW - PICKERAL POND

INSTAG ICOMP IECOM ITAPE JPLT JPR1 INAME ISTAGE IAU0
P100 0 0 0 0 0 0 0 0 0

HYDROGRAPH DATA

INTUG IUNG TAREA SHAP TRSDA TRSPC RATIO ISONH ISAME LOCAL
1 4.90 0.00 23.00 0.00 0.000 0 0 1 0

PRECIP DATA

OPPE PMS R6 R12 R24 R48 R72 R96
0.00 21.50 101.00 114.00 124.00 133.00 0.00 0.00

TRSPC COMPUTED BY THE PROGRAM IS .827

LOSS DATA

LEOFT STERN DUTRN RTING ERWIN STRES RTION STRIC CRSTE ALSHX RTINP
0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .05 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 2.00 CP= .45 RTA= 0

RECESSION DATA

STRTON= -1.50 QRCSE= -.05 RTION= 2.00
APPROXIMATE CLANK COEFFICIENTS FROM GIVEN SUTDLE CP AND TP ARE TC=13.12 AND R=19.69 INTERVALS

UNIT HYDROGRAPH 100 END-OF-PERIOD ORIGINATES, LACS 2.09 HOURS, CP= .45 VOL= .99

14.	53.	100.	174.	351.	332.	417.	499.	569.	625.
600.	890.	704.	806.	652.	620.	589.	560.	532.	506.
481.	457.	434.	413.	392.	373.	354.	337.	320.	304.
285.	275.	261.	248.	236.	224.	213.	203.	193.	183.
174.	165.	157.	149.	142.	135.	128.	122.	116.	110.
105.	100.	95.	90.	85.	81.	77.	73.	70.	66.
63.	60.	57.	54.	51.	49.	46.	44.	42.	40.
30.	30.	34.	31.	29.	29.	28.	27.	25.	24.
23.	22.	21.	20.	19.	18.	17.	16.	15.	14.
14.	13.	12.	12.	11.	11.	10.	10.	9.	9.

RAIN EXCS LOSS CUMP 0

SUM 23.00 21.26 2.40 379000.
(601.31 500.31 61.11032.31)

LOCAL INFLOW -
PICKERAL POND

PEAK	6-HR	24-HR	72-HR	TOTAL VOL.
3513.	3608.	1031.	305.	157357.
91.	76.	24.	14.	4286.
	5.10	1.83	1.48	
	129.59	198.79	202.73	202.73
	1333.	2044.	2085.	2085.
	1644.	2522.	2572.	2572.

0.40 PMF

PEAK	6-HR	24-HR	72-HR	TOTAL VOLUME
4392.	3359.	1280.	631.	109193.
124.	95.	36.	16.	5307.
	6.38	9.70	9.98	9.98
	161.99	248.49	253.41	253.41
	1666.	2555.	2606.	2606.
	2055.	3152.	3214.	3214.

0.50 PMF

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS

DATE 5-13-81

PROJ. NO. 80-238-755

CHKD. BY DLG

DATE 5-13-81

SHEET NO. N OF 222



CONSULTANTS, INC.

**Engineers • Geologists • Planners
Environmental Specialists**

	5-HOUR	2-HOUR	72-HOUR	TOTAL VOLUME
CFR	8783.	2577.	1261.	37885.
CNR	73.	36.	1013.	1013.
INCHES	12.76	19.59	19.59	19.59
MM	323.98	956.99	906.03	506.63
AC-FT	3332.	5111.	5212.	5212.
THOUS CU M	4110.	6304.	6429.	6429.

43

中国书画函授大学肇庆分校

SECRET

2019年12月31日

00000000

SECRET

COMING HYDROGRAPH

COMBINE PICKERAL POND INFLOW W/ ROUTED OUTFLOWS FROM UPSTREAM DAMS

181AU	18CMP	18EOM	18APE	18PRT	18NAME	18STAGE	18AUTO
0	0	0	0	0	0	0	0

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFR	10072	5233	3523	1708	51134
CHS	300	261	190	48	1479
INCMEX		3.73	5.73	5.74	5.74
MM		94.05	144.78	145.91	145.91
AC-PT		4570	6908	7043	7043
TRAMS CU M		5647	8620	8688	8688

0.40PMF

SUM OF LOCAL INFLOW TO
PICKERAL POND AND
OUTFLOW FROM
PORTERS LAKE,
BLUE HERON LAKE,
AND PECKS POND.

	FEAR	5-HOUR	20-HOUR	72-HOUR	TOTAL VOLUME
CFB	14677.	12391.	4651.	2245.	47967.
CNB	421.	351.	132.	64.	19167.
LUCNES		5.01	7.52	7.52	7.52
MM		127.30	191.12	192.55	192.55
AC-FY		6144.	9224.	9294.	9294.
THOUS CU-FY		7979.	11379.	11464.	11464.

0.50 PMF

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	34654.	28139.	10402.	5031.	450365.
CMS	797.	797.	395.	142.	12738.
INCHES	902.	11.30	16.83	16.96	16.96
MM		289.07	427.46	430.69	430.69
AC-FT		13993.	20033.	20789.	20789.
HMONA CU M		17211.	25450.	25643.	25643.

3/2

.....

● ● ● ● ● ● ● ●

.....

.....

.....

HYDROGRAPH ROUTING

WHITE TOTAL HYDROGRAPH THROUGH PICKERAL POND DAM

	ISIAO	IComp	ICom	ITape	Jprt	Jprt	Iname	Istage	Iauto
Ptld	1			0	0	0	1	0	0
				ROUTING DATA					
		Avg	IRes	ISame	IORT	IPMP		LSTR	
QLOSS	0.0	0.00	1	1	0	0		0	
MTPS	INSTOL	0	IAG	AMSK	X	YRK	STORA	ISPRT	
	1		0	0	0.00	0.000	-1311-	-1	

[illegible]

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DJS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81

SHEET NO.

1 OF 22

Engineers • Geologists • Planners
Environmental Specialists

SURFACE AREA 0. 155. 626. 705. 1200.
CAPACITY 0. 362. 2796. 4413. 24862.
ELEVATION 1304. 1311. 1316. 1320. 1340.
CHFL SPED CUON EXPW FLEVL CUOL CANEA EXPL
1311.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAVID DATA
TURBL CUOL EXPW DAMDIO
1317.7 0.0 0.0 0.

CHEST LENGTH 100. 100. } ARTIFICIAL VALUES REQUIRED DUE TO THE PROBLEM
AT OR BELOW 1500.0 1520.0 } AND THE SPECIFIC INPUT DATA; WILL HAVE NO
ELEVATION 1500.0 1520.0 } EFFECT ON FACILITY RATING CURVE.

0.40 PMF
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
7746. 2524. 1216. 364702.
CFS 219. 71. 34. 10337.
CMS 206. 71. 34. 10337.
INCHES 2.94 4.08 4.16 4.16
74.69 103.72 104.07 104.07
AC-FT 3405. 5007. 5023. 5023.
THOUS CU M 4447. 6176. 6196. 6196.

0.50 PMF
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
10653. 3403. 1638. 491508.
CFS 302. 96. 46. 13916.
CMS 276. 96. 46. 13916.
INCHES 3.94 5.50 5.82 5.82
100.08 139.82 140.26 140.26
AC-FT 4831. 6749. 6770. 6770.
THOUS CU M 5958. 8325. 8351. 8351.

PMF
PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
26520. 8334. 4012. 1203640.
CFS 751. 236. 114. 34081.
CMS 665. 236. 114. 34081.
INCHES 9.49 13.48 14.52 14.52
241.10 342.47 343.47 343.47
AC-FT 11638. 16531. 16579. 16579.
THOUS CU M 14355. 20390. 20450. 20450.

PICKERAL POND
DAM OUTFLOW.

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DJS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81

SHEET NO.

P

OF

22



Engineers • Geologists • Planners
Environmental Specialists

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE FEET (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN RATIO 1	RATIO 2	RATIO 3
			.40	.50	1.00
ROUTING SUMMARY					
HYDROGRAPH AT	PLPD	9.20 (23.83)	1	6401. (161.25)	8001. (226.57)
ROUTED TO	PEPD	9.20 (23.83)	1	4217. (119.41)	5016. (144.59)
HYDROGRAPH AT	HLPD	1.10 (2.88)	1	1192. (33.74)	1489. (42.18)
ROUTED TO	HLPD	1.10 (2.88)	1	427. (12.08)	555. (15.72)
HYDROGRAPH AT	LHLD	.10 (.26)	1	137. (3.87)	171. (4.84)
2 COMBINED	LHLD	1.20 (3.11)	1	456. (12.92)	593. (16.50)
ROUTED TO	LHLD	1.20 (3.11)	1	438. (12.40)	571. (16.18)
HYDROGRAPH AT	BHLD	5.00 (12.95)	1	3221. (91.21)	4026. (114.01)
2 COMBINED	BHLD	6.20 (16.06)	1	3600. (101.95)	4524. (128.10)
ROUTED TO	BHLD	6.20 (16.06)	1	3525. (99.81)	4445. (125.86)
HYDROGRAPH AT	PLP	2.70 (6.99)	1	1820. (51.33)	2275. (64.31)
ROUTED TO	PLD	2.70 (6.99)	1	1034. (29.28)	1536. (43.49)
HYDROGRAPH AT	PIPD	4.90 (12.69)	1	3513. (99.49)	4392. (124.36)
4 COMBINED	PIPD	23.00 (59.57)	1	10872. (307.67)	14877. (421.28)
ROUTED TO	PIPD	23.00 (59.57)	1	7746. (219.34)	10653. (301.65)

SUBJECT DAM SAFETY INSPECTION
PICKERAL POND DAM
 BY RTS DATE 5-13-81 PROJ. NO. 80-238-755
 CHKD. BY DLB DATE 5-13-81 SHEET NO. Q OF 20



PECKS POND DAM;
 OVERTOPS @ \approx
 0.04PMF

HEMLOCK LAKE
 DAM;
 OVERTOPS @ \approx
 0.60PMF

LOWER HEMLOCK
 DAM;
 OVERTOPS @ \approx
 0.67PMF

SUMMARY OF DAM SAFETY ANALYSIS

PECKS POND DAM									
INITIAL VALUE		SPILLWAY CREST		TOP OF DAM					
ELEVATION		1360.00		1362.30					
STORAGE		1097.		2143.					
OUTFLOW		0.		420.					
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.40	1364.11	1.81	3072.	4217.	9.33	44.50	0.00		
.50	1365.52	2.22	3298.	5016.	9.63	44.00	0.00		
1.00	1366.10	3.00	4246.	13452.	12.00	43.50	0.00		
HEMLOCK LAKE DAM									
INITIAL VALUE		SPILLWAY CREST		TOP OF DAM					
ELEVATION		1439.00		1442.00					
STORAGE		918.		1399.					
OUTFLOW		0.		806.					
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.40	1440.96	0.00	1215.	427.	0.00	43.50	0.00		
.80	1441.34	0.00	1282.	555.	0.00	43.50	0.00		
1.00	1442.70	.70	1523.	1791.	5.00	42.67	0.00		
LOWER HEMLOCK DAM									
INITIAL VALUE		SPILLWAY CREST		TOP OF DAM					
ELEVATION		1432.00		1435.30					
STORAGE		307.		394.					
OUTFLOW		0.		1012.					
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.40	1431.88	0.00	354.	438.	0.00	44.00	0.00		
.50	1434.25	0.00	364.	571.	0.00	43.83	0.00		
1.00	1436.45	1.15	429.	1846.	4.17	43.00	0.00		

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DJS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

RLB

DATE

5-13-81

SHEET NO.

R

OF

22

Engineers • Geologists • Planners
Environmental SpecialistsBLUE HERON
LAKE DAM;
OVERTOPS
@ = 0.04PMFPORTERS
LAKE
DAM;
OVERTOPS
@ = 0.02PMFPICKERAL
POND
DAM
(OVERTOPS
@ = 0.40PMF)

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	1340.39	1.89	545.	3525.	12.00	42.83	0.00
.50	1340.67	2.17	576.	4485.	12.82	42.83	0.00
1.00	1341.94	3.44	732.	9619.	16.17	42.83	0.00

INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
1315.00	1315.00	1316.50
1904.	1904.	2273.
0.	0.	39.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	1317.66	1.16	2583.	1034.	8.03	45.17	0.00
.50	1317.91	1.41	2651.	1536.	9.33	44.50	0.00
1.00	1318.68	2.19	2874.	4037.	11.80	43.33	0.00

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.40	1317.70	.00	2798.	7746.	.33	46.50	0.00
.50	1318.03	1.13	3546.	10653.	6.87	46.17	0.00
1.00	1322.00	5.10	6696.	26520.	9.00	45.00	0.00

AD-A101 246

GAI CONSULTANTS INC MONROEVILLE PA
NATIONAL DAM INSPECTION PROGRAM. PICKERAL POND DAM (NDI I.D. NU-ETC(U)
JUN 81 B M MIHALCIN
DACWS1-81-C-0015
NL

UNCLASSIFIED

2 of 2
AD-A101 246



END
DATE
FILMED
8-81
DTIC

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS DATE 5-13-81 PROJ. NO. 80-238-755

CHKD. BY DLB DATE 5-13-81 SHEET NO. 5 OF 22



Engineers • Geologists • Planners
Environmental Specialists

**BREACHING
ANALYSIS**

(INPUT SAME AS FOR
OVERTOPPING ANALYSIS,
WITH THE ADDITION OF THE
BREACH CRITERIA GIVEN HERE.)

- UNDER 0.42 PMF
CONDITIONS.

DAM SAFETY INSPECTION
PICKERAL POND DAM - BREACHING ANALYSIS - (U.S. DAMS INCLUDED)
10-MINUTE TIME STEP AND 60-MINUTE STORM DURATION

JOB SPECIFICATION									
NO	HR	MIN	DAY	INR	INTN	NETHC	IPLT	IPHT	INSTAN
100	0	10	0	0	0	0	0	0	0
JOPLR				5	0	0	0	0	0
JOPLR				5	0	0	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 5 RATIOS 1 RATIOS 1

RTIO3= .42

HYDROGRAPH ROUTING

ROUTE TOTAL HYDROGRAPH THROUGH PICKERAL POND DAM

DAM DATA			
TOPEL	CUOD	ESPD	DAMWID
1317.7	0.0	0.0	0.0

CHEST LENGTH 100. 100.
AT OR BELOW 1800.0 1820.0
ELEVATION

DAM BREACH DATA			
BWID	Z	ELBN	TRAIL
0.	2	1304.00	.50
			1311.00
			1317.70

STATION PIPD - PLAN 1, RATIO 1

BEGIN DAM FAILURE AT 45.00 HOURS

PEAK OUTFLOW IS 9713. AT TIME 45.50 HOURS

BEGIN DAM FAILURE AT 45.00 HOURS

PEAK OUTFLOW IS 26220. AT TIME 45.50 HOURS

DAM BREACH DATA			
BWID	Z	ELBN	TRAIL
100.	2	1304.00	.50
			1311.00
			1317.70

STATION PIPD - PLAN 2, RATIO 1

PLAN

①

②

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY DJS

DATE 5-13-81

PROJ. NO. 80-238-755

CHKD. BY DLB

DATE 5-13-81

SHEET NO. 1 OF 22



Engineers • Geologists • Planners
Environmental Specialists

PLAN

③

DAM BREACH DATA
E ELEM TFAIL WSEL FAILED
6. 1.00 1304.00 4.00 1311.00 1317.70
STATION PIPD . PLAN 3, RATIO 1

BEGIN DAM FAILURE AT 45.00 HOURS

PEAK OUTFLOW IS 8579. AT TIME 48.98 HOURS

④

DAM BREACH DATA
E ELEM TFAIL WSEL FAILED
100. 2.50 1304.00 4.00 1311.00 1317.70
STATION PIPD . PLAN 4, RATIO 1

BEGIN DAM FAILURE AT 45.00 HOURS

PEAK OUTFLOW IS 15274. AT TIME 48.67 HOURS

⑤

DAM BREACH DATA
E ELEM TFAIL WSEL FAILED
46. 1.00 1304.00 1.00 1311.00 1317.70
STATION PIPD . PLAN 5, RATIO 1

BEGIN DAM FAILURE AT 45.00 HOURS

PEAK OUTFLOW IS 15300. AT TIME 46.00 HOURS

SUBJECT

DAM SAFETY INSPECTION PICKERAL POND DAM

BY

JDS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81

SHEET NO.

U OF 22



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

THE DAM BREACH HYDROGRAPH WAS DEVELOPED USING A TIME INTERVAL OF .010 HOURS DURING BREACH FORMATION. DOWNSTREAM CALCULATIONS WILL USE A TIME INTERVAL OF .107 HOURS. THIS TABLE COMPARES THE HYDROGRAPH FOR DOWNSTREAM CALCULATIONS WITH THE COMPUTED BREACH HYDROGRAPH. INTERMEDIATE FLOWS ARE INTERPOLATED FROM END-UP-PERIOD VALUES.

TIME (HOURS)	TIME FROM BEGINNING OF BREACH (HOURS)	INTERPOLATED BREACH HYDROGRAPH (CFS)	COMPUTED BREACH HYDROGRAPH (CFS)	ERROR (CFS)	ACCUMULATED ERROR (CFS)	ACCUMULATED ERROR (TAC-FT)
45.000	0.000	7776.	7776.	0.	0.	0.
45.010	.010	7975.	7830.	145.	145.	0.
45.020	.020	8173.	7919.	254.	399.	0.
45.029	.029	8372.	8032.	340.	739.	1.
45.039	.039	8571.	8159.	412.	1144.	1.
45.049	.049	8769.	8316.	454.	1598.	1.
45.059	.059	8968.	8482.	486.	2084.	2.
45.069	.069	9167.	8653.	513.	2587.	2.
45.078	.078	9365.	8850.	515.	3093.	3.
45.088	.088	9564.	9067.	497.	3591.	3.
45.098	.098	9763.	9288.	475.	4065.	3.
45.108	.108	9961.	9521.	440.	4506.	4.
45.118	.118	10160.	9768.	394.	4900.	4.
45.127	.127	10359.	10022.	337.	5237.	4.
45.137	.137	10557.	10289.	268.	5505.	4.
45.147	.147	10756.	10567.	189.	5694.	5.
45.157	.157	10955.	10853.	107.	5794.	5.
45.167	.167	11153.	11153.	0.	5794.	5.
45.176	.176	11353.	11462.	72.	5866.	5.
45.186	.186	11553.	11780.	133.	5999.	5.
45.196	.196	11753.	12107.	185.	6184.	5.
45.206	.206	11953.	12445.	226.	6413.	5.
45.216	.216	12153.	12791.	262.	6674.	5.
45.225	.225	12353.	13146.	286.	6961.	6.
45.235	.235	12553.	13511.	302.	7263.	6.
45.245	.245	12753.	13886.	309.	7571.	6.
45.255	.255	12953.	14266.	307.	7876.	6.
45.265	.265	13153.	14656.	296.	8174.	7.
45.275	.275	13353.	15053.	278.	8452.	7.
45.284	.284	13553.	15461.	251.	8703.	7.
45.294	.294	13753.	15876.	216.	8919.	7.
45.304	.304	13953.	16298.	174.	9093.	7.
45.314	.314	14153.	16729.	124.	9217.	7.
45.324	.324	14353.	17166.	66.	9282.	8.
45.333	.333	14553.	17612.	0.	9282.	8.
45.343	.343	14753.	18063.	53.	9335.	8.
45.353	.353	14953.	18525.	100.	9435.	8.
45.363	.363	15153.	18992.	139.	9574.	8.
45.373	.373	15353.	19463.	170.	9744.	8.
45.382	.382	15553.	19948.	195.	9939.	8.
45.392	.392	15753.	20437.	213.	10153.	8.
45.402	.402	15953.	20931.	225.	10378.	8.
45.412	.412	16153.	21433.	230.	10607.	9.
45.422	.422	16353.	21941.	228.	10836.	9.
45.431	.431	16553.	22453.	220.	11056.	9.
45.441	.441	16753.	22975.	206.	11262.	9.
45.451	.451	16953.	23502.	186.	11449.	9.
45.461	.461	17153.	24034.	160.	11609.	9.
45.471	.471	17353.	24572.	120.	11737.	10.
45.480	.480	17553.	25116.	91.	11828.	10.
45.490	.490	17753.	25663.	48.	11877.	10.
45.500	.500	17953.	26220.	0.	11877.	10.

PLAN
②

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

JTS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLB

DATE

5-13-81


SHEET NO.

V

OF 22



Engineers • Geologists • Planners
Environmental Specialists



SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

JJS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLA

DATE

5-13-81

SHEET NO.

W OF DD



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

THE DAM BREACH HYDROGRAPH WAS DEVELOPED USING A TIME INTERVAL OF .021 HOURS DURING BREACH FORMATION.
DUNNSTEAM CALCULATIONS WILL USE A TIME INTERVAL OF .167 HOURS.
THIS TABLE COMPARES THE HYDROGRAPH FOR DUNNSTEAM CALCULATIONS WITH THE COMPUTED BREACH HYDROGRAPH.
INTERMEDIATE FLOWS ARE INTERPOLATED FROM END-OF-PERIOD VALUES.

TIME (HOURS)	TIME FROM BEGINNING OF BREACH (HOURS)	INTERPOLATED BREACH HYDROGRAPH (CFS)	COMPUTED BREACH HYDROGRAPH (CFS)	ERROR (CFS)	ACCUMULATED ERROR (CFS)	ACCUMULATED ERROR (AC-FT)
45.000	0.000	7775.	7775.	0.	0.	0.
45.021	.021	7845.	7810.	35.	35.	0.
45.042	.042	7915.	7860.	55.	90.	0.
45.063	.063	7985.	7920.	65.	155.	0.
45.083	.083	8054.	7989.	65.	220.	0.
45.104	.104	8124.	8066.	58.	279.	0.
45.125	.125	8194.	8149.	45.	324.	1.
45.146	.146	8264.	8239.	25.	350.	1.
45.167	.167	8334.	8314.	20.	370.	1.
45.188	.188	8404.	8435.	31.	395.	1.
45.209	.209	8474.	8541.	67.	462.	1.
45.229	.229	8544.	8612.	68.	530.	1.
45.250	.250	8614.	8683.	69.	599.	1.
45.271	.271	8684.	8754.	70.	668.	1.
45.292	.292	8754.	8825.	71.	737.	1.
45.313	.313	8825.	8896.	71.	806.	1.
45.333	.333	8896.	8967.	71.	875.	1.
45.354	.354	8967.	9038.	71.	944.	1.
45.375	.375	9038.	9109.	71.	1013.	1.
45.396	.396	9109.	9180.	71.	1082.	1.
45.417	.417	9180.	9251.	71.	1151.	1.
45.438	.438	9251.	9322.	71.	1220.	1.
45.458	.458	9322.	9393.	71.	1289.	1.
45.479	.479	9393.	9464.	71.	1358.	1.
45.500	.500	9464.	9535.	71.	1427.	1.
45.521	.521	9535.	9606.	71.	1496.	1.
45.542	.542	9606.	9677.	71.	1565.	1.
45.563	.563	9677.	9748.	71.	1634.	1.
45.583	.583	9748.	9819.	71.	1703.	1.
45.604	.604	9819.	9890.	71.	1772.	1.
45.625	.625	9890.	9961.	71.	1841.	1.
45.646	.646	9961.	10032.	71.	1910.	1.
45.667	.667	10032.	10103.	71.	1979.	1.
45.688	.688	10103.	10174.	71.	2048.	1.
45.708	.708	10174.	10245.	71.	2117.	1.
45.729	.729	10245.	10316.	71.	2186.	1.
45.750	.750	10316.	10387.	71.	2255.	1.
45.771	.771	10387.	10458.	71.	2324.	1.
45.792	.792	10458.	10529.	71.	2393.	1.
45.813	.813	10529.	10600.	71.	2462.	1.
45.833	.833	10600.	10671.	71.	2531.	1.
45.854	.854	10671.	10742.	71.	2600.	1.
45.875	.875	10742.	10813.	71.	2669.	1.
45.896	.896	10813.	10884.	71.	2738.	1.
45.917	.917	10884.	10955.	71.	2807.	1.
45.938	.938	10955.	11026.	71.	2876.	1.
45.959	.959	11026.	11097.	71.	2945.	1.
45.979	.979	11097.	11168.	71.	3014.	1.
46.000	1.000	11168.	11239.	71.	3083.	1.

PLAN
⑤

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DRS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY


DLB

DATE


5-13-81

SHEET NO.

X OF 22



Engineers • Geologists • Planners
Environmental Specialists



SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY ATSDATE 5-13-81PROJ. NO. 80-238-755CHKD. BY DLBDATE 5-13-81SHEET NO. Y OF 22Engineers • Geologists • Planners
Environmental Specialists

HYDROGRAPH ROUTING

ROUTE FROM DAM TO SECTION 11 5700 FT D.S. FROM DAM

ISTAU	ICUMP	IFCUM	ITAPE	JPUT	JPRY	INAME	ISTAGE	IAUTU
SEC 1	1	0	0	0	0	0	1	0

ALL PLANS HAVE SAME

CLASS	AVG	INER	ISAME	ICPT	IPMP	LASTH
0.0	0.00	0.00	1	0	0	0

MTSP	MTDOL	LAG	ANSK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-1.	0

NORMAL DEPTH CHANNEL ROUTING

ON(1)	ON(2)	ON(3)	ELAVT	ELMAX	RLNTH	SEL
0.000	0.450	1.500	1260.0	1260.0	5700.	0.0000

CROSS SECTION COORDINATES--STA. ELEV. STA. ELEV.--ETC

0.00	1260.00	500.00	1245.00	597.00	1263.00	600.00	1260.00	640.00	1260.00
643.00	1263.00	700.00	1272.00	760.00	1280.00				

STORAGE	0.00	5.65	11.60	17.92	29.42	46.01	74.56	106.07	143.23
	235.10	289.61	349.90	416.10	488.22	566.27	650.23	740.11	835.91

OUTFLOW	0.00	111.24	352.29	696.17	1194.51	1914.51	2910.77	4199.55	5809.71
	10106.12	12046.06	16010.72	19628.14	23726.23	28329.13	33460.44	39143.25	45400.16

STAGE	1260.00	1261.05	1262.11	1263.16	1264.21	1265.26	1266.32	1267.37	1268.42
	1270.53	1271.50	1272.63	1273.68	1274.74	1275.79	1276.84	1277.89	1278.95

FLOW	0.00	111.24	352.29	696.17	1194.51	1914.51	2910.77	4199.55	5809.71
	10106.12	12046.06	16010.72	19628.14	23726.23	28329.13	33460.44	39143.25	45400.16

HYDROGRAPH ROUTING

ROUTE FROM SECTION 1 TO SECTION 21 6450 FT D.S. FROM DAM

ISTAU	ICUMP	IFCUM	ITAPE	JPUT	JPRY	INAME	ISTAGE	IAUTU
SEC 2	1	0	0	0	0	0	1	0

ALL PLANS HAVE SAME

ROUTING DATA

CLASS	AVG	INER	ISAME	ICPT	IPMP	LASTH
0.0	0.00	0.00	1	0	0	0

MTSP	MTDOL	LAG	ANSK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-1.	0

SUBJECT

DAM SAFETY INSPECTION
PICKERAL POND DAMBY DJS

DATE

5-13-81

PROJ. NO.

80-238-755CHKD. BY DLB

DATE

5-13-81

SHEET NO.

AA

OF

20

CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental SpecialistsBREACH ANALYSIS
SUMMARY (6.42PMF)

PECKS POND DAM

HEMLOCK LAKE
DAMLOWER HEMLOCK
LAKE DAMBLUE HERON
LAKE DAMPORTERS LAKE
DAM

SUMMARY UP DAM SAFETY ANALYSIS

ELEVATION	INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM
STORAGE	1360.00	1360.00	1362.30
OUTFLOW	1097.	1097.	2143.
	0.	0.	420.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFE	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.42	1366.19	1.89	3119.	4551.	9.33	44.33	0.00

ELEVATION	INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM
STORAGE	1439.00	1439.00	1442.00
OUTFLOW	918.	918.	1397.
	0.	0.	806.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFE	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.42	1441.04	0.00	1228.	452.	0.00	41.50	0.00

ELEVATION	INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM
STORAGE	1432.00	1432.00	1435.20
OUTFLOW	307.	307.	394.
	0.	0.	1012.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFE	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.42	1433.96	0.00	356.	463.	0.00	44.00	0.00

ELEVATION	INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM
STORAGE	1337.00	1337.00	1338.50
OUTFLOW	201.	201.	343.
	0.	0.	320.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFE	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.42	1340.45	1.95	551.	3709.	12.17	42.93	0.00

ELEVATION	INITIAL VALUE	SPILLWAY CHEST	TOP OF DAM
STORAGE	1315.00	1315.00	1316.50
OUTFLOW	1904.	1904.	2273.
	0.	0.	39.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFE	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.42	1317.72	1.22	2596.	1133.	9.00	45.00	0.00

SUBJECT DAM SAFETY INSPECTIONPICKERAL POND DAMBY BJSDATE 5-13-81PROJ. NO. 80-238-755CHKD. BY DLBDATE 5-13-81SHEET NO. BB OF DDEngineers • Geologists • Planners
Environmental Specialists

PLAN ①.....									
	RATIO OF PMF	ELEVATION RESERVOIR STORAGE OUTFLOW	INITIAL VALUE 1311.00 362. 0.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	SPILLWAY CREST 1311.00 362. 0.	TOP OF DAM 1317.70 2796. 7740.	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.42	1317.03	.13	2877.	9713.	1.83	45.50	45.00	
PICKERAL POND DAM.									
PLAN ②.....									
	RATIO OF PMF	ELEVATION RESERVOIR STORAGE OUTFLOW	INITIAL VALUE 1311.00 362. 0.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	SPILLWAY CREST 1311.00 362. 0.	TOP OF DAM 1317.70 2796. 7740.	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.42	1317.75	.05	2826.	26220.	.44	45.50	45.00	
PICKERAL POND DAM.									
PLAN ③.....									
	RATIO OF PMF	ELEVATION RESERVOIR STORAGE OUTFLOW	INITIAL VALUE 1311.00 362. 0.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	SPILLWAY CREST 1311.00 362. 0.	TOP OF DAM 1317.70 2796. 7740.	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.42	1317.95	.25	2955.	9579.	3.00	48.58	45.00	
PICKERAL POND DAM.									
PLAN ④.....									
	RATIO OF PMF	ELEVATION RESERVOIR STORAGE OUTFLOW	INITIAL VALUE 1311.00 362. 0.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	SPILLWAY CREST 1311.00 362. 0.	TOP OF DAM 1317.70 2796. 7740.	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.42	1317.85	.15	2892.	15274.	1.54	48.67	45.00	
PICKERAL POND DAM.									
PLAN ⑤.....									
	RATIO OF PMF	ELEVATION RESERVOIR STORAGE OUTFLOW	INITIAL VALUE 1311.00 362. 0.	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	SPILLWAY CREST 1311.00 362. 0.	TOP OF DAM 1317.70 2796. 7740.	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
	.42	1317.80	.10	2860.	15300.	.96	46.00	45.00	

SUBJECT DAM SAFETY INSPECTION

PICKERAL POND DAM

BY RTS DATE 5-17-81 PROJ. NO. 80-238-755

CHKD. BY DLG DATE 5-13-81 SHEET NO. CC OF DD



CONSULTANTS, INC.

Engineers • Geologists • Planners
Environmental Specialists

PLAN ⑤..... (NON-BREACH)		INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
		1311.00	1311.00	1317.70
		362.	362.	2796.
		0.	0.	7740.
		ELEVATION		
		STORAGE		
		OUTFLOW		
RATIO	MAXIMUM	MAXIMUM	DURATION	TIME OF
UP	RESERVOIR	STORAGE	OVER TOP	MAX OUTFLOW
PHF	4.5. ELEV	AC-FT	HOURS	FAILURE
.42	1317.96	2959.	3.50	46.50
				0.00
PLAN ① STATION SECT				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	9593.	1270.3	46.33	
PLAN ② STATION SECT				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	22892.	1274.5	45.83	
PLAN ③ STATION SECT				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	8577.	1269.8	48.83	
PLAN ④ STATION SECT				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	15225.	1272.4	49.00	
PLAN ⑤ STATION SECT				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	14412.	1272.1	46.33	
PLAN ⑥ STATION SECT				
(NON-BREACH)				
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	TIME
	FLOW, CFS	STAGE, FT	STAGE, FT	HOURS
.42	8238.	1269.7	46.67	

SECTION 1

SUBJECT

DAM SAFETY INSPECTION

PICKERAL POND DAM

BY

DJS

DATE

5-13-81

PROJ. NO.

80-238-755

CHKD. BY

DLG

DATE

5-13-81

SHEET NO.

22

OF 22

Engineers • Geologists • Planners
Environmental Specialists

PLAN ① STATION SEC3				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	9481.	1253.8	46.03	
PLAN ② STATION SEC3				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	20916.	1256.9	46.33	
PLAN ③ STATION SEC3				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	8568.	1253.5	49.00	
PLAN ④ STATION SEC3				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	15076.	1255.5	49.17	
PLAN ⑤ STATION SEC3				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	13796.	1255.2	46.03	
PLAN ⑥ STATION SEC3 (NON-BREACH)				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	8209.	1253.3	47.17	

SECTION

3

PLAN ① STATION SEC2				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	9595.	1264.5	46.33	
PLAN ② STATION SEC2				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	22894.	1268.6	45.83	
PLAN ③ STATION SEC2				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	8576.	1264.1	48.83	
PLAN ④ STATION SEC2				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	19226.	1266.4	49.00	
PLAN ⑤ STATION SEC2				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	14414.	1266.2	46.33	
PLAN ⑥ STATION SEC2 (NON-BREACH)				
RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS	
.42	8237.	1264.0	46.83	

SECTION

2

LIST OF REFERENCES

1. "Recommended Guidelines for Safety Inspection of Dams," prepared by Department of the Army, Office of the Chief of Engineers, Washington, D. C. (Appendix D).
2. "Unit Hydrograph Concepts and Calculations," by the U. S. Army, Corps of Engineers, Baltimore District (L-519).
3. "Seasonal Variation of Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1,000 Square Miles and Durations of 6, 12, 24, and 48 Hours," Hydrometeorological Report No. 33, prepared by J. T. Reidel, J. F. Appleby and R. W. Schloemer, Hydrologic Service Division, Hydrometeorological Section, U. S. Army, Corps of Engineers, Washington, D. C., April 1956.
4. Design of Small Dams, U. S. Department of the Interior, Bureau of Reclamation, Washington, D. C., 1973.
5. Handbook of Hydraulics, H. W. King, and E. F. Brater, McGraw-Hill, Inc., New York, 1963.
6. Standard Handbook for Civil Engineers, F. S. Merritt, McGraw-Hill, Inc., New York, 1963.
7. Open-Channel Hydraulics, V. T. Chow, McGraw-Hill, Inc., New York, 1959.
8. Weir Experiments, Coefficients, and Formulas, R. E. Horton, Water Supply and Irrigation Paper No. 200, Department of the Interior, United States Geological Survey, Washington, D. C., 1907.
9. "Probable Maximum Precipitation, Susquehanna River Drainage Above Harrisburg, Pennsylvania," Hydrometeorological Report No. 40, prepared by H. V. Goodyear and J. T. Riedel, Hydrometeorological Branch Office of Hydrology, U. S. Weather Bureau, U. S. Department of Commerce, Washington, D. C., May, 1965.
10. Flood Hydrograph Package (HEC- 1) Dam Safety Version, Hydrologic Engineering Center, U. S. Army, Corps of Engineers, Davis, California, July 1978.
11. "Simulation of Flow Through Broad Crest Navigation Dams with Radial Gates," R. W. Schmitt, U. S. Army, Corps of Engineers, Pittsburgh District.
12. "Hydraulics of Bridge Waterways," BPR, 1970, Discharge Coefficient Based on Criteria for Embankment Shaped Weirs, Figure 24, page 46.

13. Applied Hydraulics in Engineering, H. M. Morris and J. N. Wiggert, Virginia Polytechnic Institute and State University, 2nd Edition, The Ronald Press Company, New York, 1972.
14. Standard Mathematical Tables, 21st Edition, The Chemical Rubber Company, 1973, page 15.
15. Engineering Field Manual, U. S. Department of Agriculture, Soil Conservation Service, 2nd Edition, Washington, D. C., 1969.
16. Water Resources Engineering, R. K. Linsley and J. B. Franzini, McGraw-Hill, Inc., New York, 1972.
17. Engineering for Dams, Volume 2, W. P. Creager, J. D. Justin, J. Hinds, John Wiley & Sons, Inc., New York, 1964.
18. Roughness Characteristics of Natural Channels, H. H. Barnes, Jr., Geological Survey Water-Supply Paper 1849, Department of the Interior, United States Geological Survey, Arlington, Virginia, 1967.
19. "Hydraulic Charts for the Selection of Highway Culverts," Hydraulic Engineering Circular No. 5, Bureau of Public Roads, Washington, D. C., 1965.

APPENDIX E
FIGURES

LIST OF FIGURES

<u>Figure</u>	<u>Description/Title</u>
1	Regional Vicinity Map
2	Watershed Boundary Map
3	Plan and Cross Sections




FIGURE 1
REGIONAL VICINITY MAP

----- LONGEST WATERCOURSE
⊙ CENTROID OF DRAINAGE AREA











FIGURE 2

WATERSHED BOUNDARY MAP






PORTION OF DUBOIS AND HANLEY QUADRANGLES, U.S. GEOLOGICAL SURVEY, SHOWING LOCATION OF DAM AND DRAINAGE AREA.
SCALE: 1" = 1 MILE



SPILLWAY CONSTRUCTION JOINT
Scale: 1" = 10'



Note: New gate to be furnished by Porters Lake Club. Repairs to be made by existing concrete gate structure and additional structural members to be provided by Contractor of bid and plans in accordance with field examination and instructions of the Engineer.

PLAN OF PROPOSED DAM
PREPARED FOR
+ PORTERS LAKE HUNTING & FISHING CLUB +
PORTERS LAKE, PIKE CO., PA.
May 14, 1946
Scale as shown.

By and for J. H. 1936
Edward C. Mason
Civil Engineer
Shenandoah, Pa.

APPENDIX F

GEOLOGY

Geology

Pickeral Pond Dam is located in the glaciated Low Plateaus section of the Appalachian Plateaus physiographic province of eastern Pennsylvania. In this area, the Appalachian Plateaus province is characterized topographically by flat-topped, hummocky hills formed as a result of glaciation and subsequent stream dissection of nearly flat-lying strata. The Devonian age sedimentary rock strata in Pike County regionally strike N35°E and dip gently to the northwest. The Delaware River is the major drainage basin in the area. Major tributary streams intersect the Delaware River at right angles; whereas, smaller streams display a slightly more random tributary pattern. Both major and minor tributary stream systems are joint controlled and exhibit modified rectangular and trellis-type drainage patterns.


Structurally, the area containing Pike County lies on the south flank of a broad, asymmetrical synclinorium that plunges to the southwest. Superimposed on this broad structural basin are numerous anticlinal and synclinal folds characterized by planar limbs and narrow hinges. Due to prior glaciation, low relief and surficial soil cover, fold axes are difficult to trace.

The sedimentary rock sequences in the vicinity of the dam and reservoir are probably members of the Susquehanna Group of Upper Devonian age (see Geology Map). The sedimentological changes observed in the Catskill Formation indicate that the rate of sedimentation exceeded the rate of basin subsidence, resulting in a facies change from marine to non-marine strata. On the accompanying geology map the delineation between the Middle and Upper Devonian age sedimentary rock sequences represents the Allegheny Front which separates the Valley and Ridge physiographic province from the Appalachian Plateaus physiographic province.

Approximately half of Pike County, including the dam site, is covered by a blanket of Wisconsin age (most recent) glacial drift which, based on the degree of weathering, was probably deposited during the Woodfordian stage. Valley bottoms are typically covered by recent alluvium and Woodfordian outwash of variable thickness, but typically less than 10 feet. These deposits are characteristically unconsolidated stratified sand and gravel, usually with more gravel than sand and some small boulders. The direction of the Wisconsin ice advance was from the northeast over the Catskill Mountains and from the north over the Appalachian Plateau. The terminal moraine resulting from the southern most advance of the Wisconsin ice sheet in this area is located in the southern portion of Monroe County, which borders Pike County to the South.

References:

1. Fletcher, F. W., Woodrow, D. L., "Geology and Economic Resources of the Pennsylvania Portion of the Milford and Port Jervis 15 minute U.S.G.S. Topographic Quadrangles," Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 223, 1970.
2. Sevon, W. D., Berg, T. M., "Geology and Mineral Resources of the Skytop Quadrangle, Monroe and Pike Counties, Pennsylvania", Pennsylvania Geological Survey, Fourth Series, Harrisburg, Atlas 214A., 1978.
3. Sevon, W., Personal Communication, Commonwealth of Pennsylvania Department of Environmental Resources, Harrisburg, December 3, 1980.



LEGEND

UPPER DEVONIAN



SUSQUEHANNA GROUP

Catskill Formation - Shohola Member interbedded 1- to 25-foot thick units of greenish-gray, silty grayish-red very fine to medium-grained sandstone and sandy shale and lesser medium-gray to medium-fine-grained sandstone and shale. Sandstones are predominantly low-rank graywackes. Beds are thin to very thick and most have simple or planar beds of small- to medium-scale, generally low-angle open stratification. Contacts with shale units are abruptly disconformable to gradational. Sandstones are poorly cemented. Shales are thinly laminated and well cleaved. Mud cracks, convolute bedding, and sole marks are present near contacts with sandstone units. Member is more than 2,000 feet thick. Lower contact is gradational and is placed at top of highest red bed of the underlying Anasink. Anasink Red Shale Member, medium-grayish-red, silty, micaceous, finely laminated well-cleaved shale containing thin beds of brownish-gray carbonaceous and silty very fine grained sandstone. Unit is the "first red" going up section in typical Anasink sequence. Member is about 100 feet thick. Lower contact is gradational and is placed at the base of lowest red bed. Delaware River Flaga Member, grayish-green, micaceous, laminated sandstone and lesser interbedded sandy shale. Beds range from a few inches to as much as 4 feet thick. Sandstones are low-rank graywackes and contain no marine fossils. Member is about 300 feet thick. Lower contact is gradational.

MIDDLE DEVONIAN



HAMILTON GROUP

Mahantango Formation - Upper member medium-dark-gray, fairly coarse grained, thin-bedded sandstone and silty shale; member is about 700 feet thick and is separated from lower member by the "Centerfield Reef," a calcareous chertstone containing abundant horn corals. The Centerfield is about 25 feet thick. Lower member, virtually same lithology as upper member. Unit is about 1,400 feet thick. Lower contact is gradational.

Marcellus Shale - Dark-gray, evenly laminated, silty clay shale and clayey silt shale. Unit normally contains very hard limy concretions and is well cleaved; bedding is generally chevroned. Member is about 25-feet thick. Lower contact is gradational.

SCALE



REFERENCE:

GEOLOGIC MAP OF NORTHEASTERN PENNSYLVANIA. COMPILED BY GEO. W. STOSE AND O.A. LJUNGSTEDT COMMONWEALTH OF PENNSYLVANIA DEPT. OF INTERNAL AFFAIRS DATED 1932. SCALE 1" = 6 MILES.

GEOLOGY MAP

gai
CONSULTANTS, INC.